

S  
627.8  
W3trp  
1969

STATE OF MONTANA  
WATER RESOURCES BOARD


TONGUE RIVER PROJECT

BASIC DESIGN REPORT



BECHTEL CORPORATION  
SAN FRANCISCO

1969



STATE OF MONTANA  
WATER RESOURCES BOARD

PROPERTY OF  
THE U.S. RECLAMATION DIVISION  
LIBRARY

TONGUE RIVER PROJECT

BASIC DESIGN REPORT



BECHTEL CORPORATION  
SAN FRANCISCO

1969

WIN 96-57091



Digitized by the Internet Archive  
in 2015

<https://archive.org/details/tongueriverproje1969bech>

## TABLE OF CONTENTS

	<u>Page</u>
I-1 SUMMARY	I-1
II INTRODUCTION	II-1
Purpose and Scope	II-1
Description of Tongue River System	II-1
History of Water Use in the Tongue River System	II-2
History of the Tongue River Project	II-2
Supporting Data	II-5
III WATER SUPPLY STUDIES	III-1
General	III-1
Yellowstone River Compact	III-1
Historical Inflow to the Tongue River Project	III-2
Future Depletion in Wyoming	III-3
Required Releases	III-3
Storable Inflow	III-3
Storable Inflow Calculation	
Realistic Allocation	III-4
Minimum Storable Inflow-Firm Yield- Storage	III-4
Losses	III-5
Siltation	III-5
Analysis	III-6
Determination of Firm Yield - Operation Study	III-6
Conclusions	III-6
Reservoir Filling Studies	III-6
IV FLOOD HYDROLOGY	IV-1
Historical Floods	IV-1
Flood of June 1964	IV-1
Probable Maximum Flood	IV-1
Probable Maximum Precipitation	IV-1
Unit Hydrograph - 3 Hours Duration	IV-2
Infiltration	IV-2
Design Inflow Flood Hydrograph	IV-2
Snow Melt Analysis	IV-3
Envelope Curve	IV-3
Standard Project Flood	IV-3
Tailwater Rating Curve	IV-3
References	IV-4



		<u>Page</u>
V	GEOLOGIC SUMMARY	V-1
	Investigations	V-1
	General Geology	V-1
	Local Geology	V-1
	Coal Beds and Baked Rock	V-2
	Natural Gas Seeps	V-3
	High Tongue River Dam Site	V-3
	Seismicity	V-6
	Geologic Conclusions	V-6
VI	CONSTRUCTION MATERIALS	VI-1
	Borrow Area Explorations	VI-1
	Tongue River Dam	VI-1
	High Tongue River Dam Site	VI-2
	Concrete Aggregates	VI-3
	Riprap	VI-4
	Testing	VI-4
VII	EMBANKMENT	VII-1
	General	VII-1
	Dam Alignment	VII-1
	Dam Section	VII-1
	Embankment and Foundation Seepage	VII-3
	Stability Analysis	VII-4
	Foundation Seepage Control	VII-5
	Right Abutment Slide Area	VII-5
	Instrumentation	VII-5
	Camber	VII-6
	Roads	VII-6
VIII	SPILLWAY	VIII-1
	General	VIII-1
	Hydraulic Design	VIII-1
	Structural Design	VIII-1
	References	VIII-3
IX	OUTLET WORKS	IX-1
	General	IX-1
	Hydraulic Design	IX-1
	Structural Design	IX-2
X	COST ESTIMATE	X-1





# LIST OF DRAWINGS

<u>No.</u>	<u>Title</u>	<u>Following Page</u>
6694-II-001	Project Location and Vicinity Maps	II-5
6694-II-002	Tongue River Basin Map	
6694-II-003	Site Map	
6694-III-001	Water Supply Studies - Minimum Storable Inflow	III-7
6694-III-002	Water Supply Studies - Reservoir Area and Capacity	
6694-III-003	Water Supply Studies-Yield- Storage-Storage Elevation	
6694-V-007	Geologic Map	V-6
6694-V-007A	Location of Drill Holes and Sections	
6694-V-008	Geologic Sections - Sheet 1 of 2	
6694-V-008A	Geologic Sections - Sheet 2 of 2	
6694-V-009	Measured Stratagraphic Sections	
6694-V-012	Graphic Drill Logs - Sheet 1 of 5	
6694-V-013	Graphic Drill Logs - Sheet 2 of 5	
6694-V-014	Graphic Drill Logs - Sheet 3 of 5	
6694-V-015	Graphic Drill Logs - Sheet 4 of 5	
6694-V-016	Graphic Drill Logs - Sheet 5 of 5	
6694-VII-001	Stage I Dam Plan	VII-6
6694-VII-002	Stage I Dam Maximum Section	
6694-VII-003	Dam Abutment Section and Detail	
6694-VII-004	Dam Seepage Control Plan	
6694-VII-005	Grouting Details	
6694-VII-006	Dam Drainage Details	
6694-VII-007	Stage II Dam Plan	
6694-VII-008	Stage II Dam Maximum Section	
6694-VII-020	Dam Stability Summary Upstream Maximum Section Sheet 1	
6694-VII-021	Dam Stability Summary Upstream Maximum Section Sheet 2	
6694-VII-022	Dam Stability Summary Upstream Abutment Section	
6694-VII-023	Dam Stability Summary Downstream Maximum Section Sheet 1	
6694-VII-024	Dam Stability Summary Downstream Maximum Section Sheet 2	
6694-VII-025	Dam Stability Summary Downstream Abutment Section	
6694-VIII-001	Spillway Plan	VIII-3
6694-VIII-002	Spillway Profile and Sections	
6694-VIII-003	Spillway Crest Structure Details	
6694-VIII-004	Spillway Approach Walls - General Arrangement	
6694-VIII-005	Spillway Crest Walls - General Arrangement	
6694-VIII-006	Spillway Chute Walls - Details	
6694-VIII-007	Spillway Chute Slab - Details	
6694-VIII-008	Spillway Stilling Basin - General Arrangement	
6694-VIII-009	Spillway-Stilling Basin Details	
6694-VIII-010	Spillway-Drainage-Layout and Detail	



<u>No.</u>	<u>Title</u>	<u>Following Page</u>
6694-VIII-011	Spillway Bridge - General Arrangement	
6694-VIII-012	Spillway-Bridge-Structural Steel Details	
6694-VIII-013	Spillway-Rating Curve and Stage II Crest	
6694-IX-001	Outlet Works-Plan,Profile and Sections	IX-2
6694-IX-002	Outlet Works-Intake Structure Concrete Outline	
6694-IX-003	Outlet Works-Valve Chamber Concrete Outline	
6694-IX-004	Outlet Works-Outlet Structure- Concrete Outline	



## I SUMMARY

This report presents the basis for the design of the Tongue River Project which is to develop industrial water supplies in southeastern Montana.

Since the late 1800's, water from the Tongue River has been used for irrigation and domestic purposes. Municipal uses have also been more recently developed. In Montana irrigation has been by direct diversion from the main Tongue River with water rights dating from 1886. In 1939, the Montana State Water Conservation Board constructed the Tongue River Dam to impound the Tongue River Irrigation Reservoir, the major storage reservoir in the basin, for irrigation and other beneficial uses.

In the high plains country of northeastern Wyoming and southeastern Montana, extensive deposits of coal are available for development. Technological advances in the use of coal-fired steam power plants and development of economical methods of converting coal to petroleum products are presently making exploitation of these vast coal deposits economically feasible. Such developments require substantial quantities of water for cooling and process consumption. Therefore, it is anticipated that further uses of water, particularly in the Tongue River Basin, will be largely for industrial purposes.

The Montana legislature in 1967 authorized the Montana Water Resources Board to carry out investigations and engineering for the Tongue River Project to develop industrial water supplies for use in southeastern Montana.

As a first step in the engineering studies, the determination of the relationship between water supply, firm yield and reservoir sizing was undertaken.

Historical flow records for the Tongue River near the state line are available since 1929, providing an adequate basis for water yield studies. However, the Tongue River, a major tributary of the Yellowstone River, flows from Wyoming into Montana and both of these states share in rights to use its waters.

To provide a basis for usage of waters of the major rivers which flow from Wyoming into Montana, these two states concluded the Yellowstone River Compact in 1950. Before yield studies could be made, it was necessary to determine Montana's share of the unused and unappropriated water in the Tongue River.

A Water Allocation Study was made presenting two "allocations". The first, adhering strictly to the compact provisions particularly with respect to reservations of supplemental water, leads to conclusions which are believed unrealistic. The second "realistic allocation" was made based on analysis and judgement of realistic future conditions in the Tongue River Basin. Under the realistic allocation it was determined that a maximum firm yield of 112,000 acre feet annually could be developed by providing 450,000 acre feet of gross storage. Such storage, however, using the furthest downstream feasible damsite would require storing water across the border into Wyoming.



Therefore, a "Stage I" High Tongue River Dam has been planned using a storage elevation 3438, some three and one-half feet below the state line streambed elevation. This Stage I reservoir has 320,000 acre feet of gross storage and a firm yield of 100,000 acre feet annually. Part of the firm yield is allocated to agricultural uses under agreements for the existing Tongue River Irrigation Reservoir. The dam is designed for future raising to provide 450,000 acre feet of storage.

In addition to the firm yield, discharges of 342 cubic feet per second are provided to satisfy adjudicated and Indian water rights and 75 cubic feet per second of winter releases.

A study was made to determine the probable time required for first filling of the reservoir. It appears that a filling period of four to six years should be provided.

The Stage I dam is about 200 feet high, 3200 feet long and contains over 10,000,000 cubic yards of earth materials. The spillway has been designed to pass probable maximum flood which has a peak inflow of 183,000 cubic feet per second. The outlet works has been designed to pass 3000 cubic feet per second at maximum storage elevation.

The total specific construction cost, based on fourth quarter 1968 price levels is \$22,133,000. Allowances for contingencies, engineering, construction management and escalation during construction bring the project cost to \$32,229,000. Additional costs to be determined by the Montana Water Resources Board include cost of land and rights of way, escalation to start of construction, owner costs and financing costs of interest during construction and interest during first reservoir filling.





## II. INTRODUCTION

### PURPOSE AND SCOPE

This report presents the basis for the design of the Tongue River Project. This Project for the Montana Water Resources Board will develop additional industrial water supplies from the Tongue River in southeastern Montana in addition to the irrigation supplies already developed. The Location and Vicinity Maps of the Tongue River Project are shown on Drawing 6694-11-001.

Summaries of hydrologic, geologic, and material exploration investigations are included. The history of water development in the Tongue River Basin is presented along with a description of the evolution of the Tongue River Project. The criteria and bases for design of the project features are summarized and discussed.

### DESCRIPTION OF THE TONGUE RIVER SYSTEM

The Tongue River rises in the Big Horn Mountains of northern Wyoming and flows north and eastward through Wyoming into Montana, finally joining the Yellowstone River at Miles City in eastern Montana. The Tongue River Basin is approximately 150 miles long and 40 miles wide, and includes some 5420 square miles of drainage area.

The major water-producing area of the Tongue River drainage lies in the Big Horn Mountains in the basins of the tributaries North Tongue River, South Tongue River, Little Tongue River, Wolf Creek, Goose Creek, and Little Goose Creek. These tributaries flow north and east from the mountains and out onto the high plains, joining together to form the main Tongue River north of Sheridan, Wyoming. A number of ephemeral streams join the main Tongue River from the north. Prairie Dog Creek rises in the plains south and east of Sheridan and joins the main Tongue River just before it crosses the border into Montana.

In Montana, many small ephemeral tributaries flow into the northward-flowing Tongue River from the west. On the east, however, drainage is dominated by three major tributaries: Hanging Woman Creek, which joins the main river at Birney; Otter Creek, which joins at Ashland; and Pumpkin Creek, which flows into the Tongue River about 22 river miles above the confluence of the Tongue and Yellowstone Rivers at Miles City. A map showing the Tongue River Drainage Basin is presented on Drawing 6694-11-002.



## HISTORY OF WATER USE IN THE TONGUE RIVER SYSTEM

Since the late 1300's, water from the Tongue River has been used for irrigation and domestic purposes. Municipal uses have also been more recently developed but the predominant use has been for irrigation.

In Wyoming, earliest water rights for irrigation date from before 1880. Extensive development of irrigation canal systems has taken place in Wyoming leading to exchange of water between tributary basins. Several reservoirs for storage of irrigation water as well as numerous stock ponds have been constructed. Importation of water from Piney Creek, a tributary of the Powder River, into the Tongue River Basin has been accomplished through the construction of irrigation canals.

In Montana, the predominant use of water has been for irrigation by direct diversion from the main Tongue River with irrigation water rights dating from 1886. In 1939, the Montana State Water Conservation Board constructed the Tongue River Dam to impound the Tongue River Irrigation Reservoir, the major storage reservoir in the basin, for irrigation and other beneficial uses. On the tributaries, wild flooding for irrigation has been widely practiced.

In the high plains country of northeastern Wyoming and southeastern Montana, extensive deposits of coal are available for development at shallow depth. Technological advances in the use of coal-fired steam-electric power generating plants and development of economical methods of converting coal to petroleum products are presently making exploitation of these vast coal deposits economically feasible. However, such developments require substantial quantities of water for cooling and process consumption. Therefore, it is anticipated that further uses of water in these areas and particularly in the Tongue River Basin will be largely for industrial purposes.

## HISTORY OF THE TONGUE RIVER PROJECT

The Montana legislature in 1967 authorized the Montana Water Resources Board to carry out investigations and engineering for the Tongue River Project to develop industrial water supplies for use in southeastern Montana. On May 25, 1967, a contract was executed between the Montana Water Resources Board and Bechtel Corporation to carry out the investigations and engineering. At that time it was anticipated that the storage required for the project would be about 150,000 acre feet to be accomplished by raising the existing Tongue River Dam, and/or building a new dam downstream.



As a first step in the engineering studies, the determination of the relationship between firm water supply yield and reservoir sizing was undertaken.

Historical flow records for the Tongue River near the state line are available since 1929, providing an adequate basis for water yield studies. However, the Tongue River, a major tributary of the Yellowstone River, flows from Wyoming into Montana and both of these states share in rights to use its waters.

In order to provide a basis for usage of waters of the major rivers which flow from Wyoming into Montana, these two states concluded the Yellowstone River Compact in 1950. Before yield studies could be made, it was necessary to determine Montana's share of the unused and unappropriated water in the Tongue River.

On June 8, 1967, the Montana Water Resources Board authorized Bechtel Corporation to proceed with a study for determination of the unused and unappropriated water in the Tongue River for allocation under the Yellowstone River Compact. That study included:

1. Collection and evaluation of basic streamflow data.
2. Collection and evaluation of water rights data in both Montana and Wyoming.
3. Field investigation of water use and administration.
4. Determination of supplemental water requirements, and
5. Analysis of data and determination of unused and unappropriated water.

After intensive study, analysis, review by the Montana Water Resources Board and revision, a draft Water Allocation study report was presented to the Yellowstone River Compact commission at Sheridan, Wyoming, on December 19, 1967. On the basis of this initial water allocation study, yield studies showed that the maximum yield from the Tongue River which could be developed from water allocated to Montana was 72,000 acre feet a year and a gross storage of 245,000 acre feet was required to develop that yield.

Following a presentation of the allocation and yield studies to the Board in Billings on January 4, 1968, further studies were made by the Board on the allocation study. Following a meeting between the Montana Water Resources Board Director and the Wyoming State Engineer on January 24, 1968, it was determined by the Board that the storage rights of the existing Tongue River Reservoir be considered as not being subject to allocation regardless of possible future changes of actual





use. The effective result of this change of interpretation was to increase the water which could be developed by Montana and therefore the yield of the project. Under this revised allocation it was determined that a maximum yield of 112,000 acre feet annually could be developed by providing some 450,000 acre feet of gross storage.

A revised draft of the Water Allocation study report was reviewed with the Board and with members of the legislative council on April 5, 1968 at Helena. The Water Allocation Study report was submitted to the Board in final form on April 22, 1968.

The Water Allocation Study presented two "allocations". The first adhering strictly to the compact provisions, particularly with respect to reservations of supplemental water, leads to conclusions which are believed unrealistic. The second "allocation" was made based on analysis and judgment of realistic future conditions in the Tongue River Basin. The Board concurred in Bechtel's recommendation that the project be sized on the basis of the "realistic allocation". The yield studies based on that allocation are described later in this report.

During the summer and autumn of 1967, field investigations were carried out to provide data for design of the increased reservoir, either by raising the existing dam, or by constructing a new dam downstream. Foundation explorations were carried out at the existing dam and at the Oxbow site, located as shown on Drawing No. 6694-11-003. Because of unfavorable foundation conditions at the Oxbow site, another site, called the Four Mile Creek site, was also explored. Borrow explorations were also carried out at this time to locate and obtain samples of earth construction materials.

During the fall of 1967 and the early winter of 1967-1968, design studies for raising the existing dam or constructing a new one downstream were carried out. Based on the initial allocation and yield studies, preliminary designs providing total storage of 245,000 acre feet were undertaken. During this period the Board determined that storage of water in Wyoming should be avoided. This criterion effectively limits the storage to about Elevation 3441, which is the approximate elevation of the Tongue River streambed at the State Line.

In January 1968, after preliminary designs had been well advanced, the revision of the allocation and yield studies required further substantial changes in the scope of the project. Studies of foundation conditions and raising the existing Tongue River dam indicated that only a moderate raise would be possible. The yield studies based on the revised and "realistic allocation" study have shown that some 450,000 acre-feet gross storage would be required for development of the 112,000 acre feet per year firm yield. Only about 140,000 acre feet of storage would be available at the existing dam site, yielding about 72,000 acre feet per year. The damsite near the Four Mile Creek confluence with the Tongue River is the furthest downstream feasible damsite before the Tongue River canyon opens out into a broader valley.





Therefore it is the site with the greatest storage potential without storing water above the State Line into Wyoming.

A dam at the Four Mile Creek site would store water to the same elevation as the existing dam raised to its greatest feasible height. However the Four Mile Creek site would provide substantially more yield. If the existing dam were raised, at an estimated direct construction cost at 1968 price level of about \$4,000,000 and additional water needed at a later date, the raised dam would be inundated and the investment would not be fully recovered. Therefore, it was recommended to the Board that a dam be built at the Four Mile Creek site and raised later if necessary to provide greater storage and greater yield.

On April 5, 1968, the Board directed Bechtel to proceed with design of a dam at the Four Mile Creek site, later designated as the High Tongue River Dam. The Board directed that the dam have a maximum storage Elevation 3438, about three and one-half feet below the State Line streambed elevation. Although this will prevent storage of water in Wyoming, floods which may occur when the reservoir is nearly full, will cause ponding of water in Wyoming. The Storage Elevation 3438 will provide gross storage of 320,000 acre feet with a corresponding yield of 100,000 acre feet annually, part of which is for agricultural use under existing commitments.


There is a possibility that a dam may be constructed for industrial purposes near the State Line in Wyoming. Such a development is considered reasonable because of physical feasibility of a damsite at that location and all Tongue River drainage in Wyoming would be tributary to such a reservoir. Such construction would make possible raising High Tongue River Dam if suitable arrangements could be made to back water up on the downstream side of the new dam. The Board therefore directed that the High Tongue River dam be designed so that it could be raised to storage elevation 3453, to provide 450,000 acre feet storage with a corresponding firm yield of 112,000 acre feet annually.

This report provides the basic design, data and construction cost estimates for the High Tongue River Dam. The yield studies, geology, construction materials, are described. The criteria for and design of the earth dam, spillway and outlet works are presented.


#### SUPPORTING DATA

Data which supports the design is presented in the supporting data volume. Topographic maps of the reservoir are presented. Included are calculations of storable inflow for the realistic allocation. The geological report on damsites, rock mechanics laboratory tests on the coal and soil test data are presented. Also included is a full treatment of the data on the existing Tongue River Dam, including preliminary raising design, a history with emphasis on seepage problems, construction drawings and photographs and reports on various grouting programs.





LOCATION MAP



VICINITY MAP

BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	PROJ ENGR	DRN ENGR	CHECKED
DRAWN	MGR SF PROJ	MGR ENGR	
CHECKED			

HIGH TONGUE RIVER DAM PROJECT LOCATION AND VICINITY MAPS  TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA							
APPROVED	DATE		DRAWING NO.		REV.		
6694			6694 - II - 001				






1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104	105	106	107	108	109	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000	1001	1002	1003	1004	1005	1006	1007	1008	1009	1010	1011	1012	1013	1014	1015	1016	1017	1018	1019	1020	1021	1022	1023	1024	1025	1026	1027	1028	1029	1030	1031	1032	1033	1034	1035	1036	1037	1038	1039	1040	1041	1042	1043	1044	1045	1046	1047	1048	1049	1050	1051	1052	1053	1054	1055	1056	1057	1058	1059	1060	1061	1062	1063	1064	1065	1066	1067	1068	1069	1070	1071	1072	1073	1074	1075	1076	1077	1078	1079	1080	1081	1082	1083	1084	1085	1086	1087	1088	1089	1090	1091	1092	1093	1094	1095	1096	1097	1098	1099	1100	1101	1102	1103	1104	1105	1106	1107	1108	1109	1110	1111	1112	1113	1114	1115	1116	1117	1118	1119	1120	1121	1122	1123	1124	1125	1126	1127	1128	1129	1130	1131	1132	1133	1134	1135	1136	1137	1138	1139	1140	1141	1142	1143	1144	1145	1146	1147	1148	1149	1150	1151	1152	1153	1154	1155	1156	1157	1158	1159	1160	1161	1162	1163	1164	1165	1166	1167	1168	1169	1170	1171	1172	1173	1174	1175	1176	1177	1178	1179	1180	1181	1182	1183	1184	1185	1186	1187	1188	1189	1190	1191	1192	1193	1194	1195	1196	1197	1198	1199	1200	1201	1202	1203	1204	1205	1206	1207	1208	1209	1210	1211	1212	1213	1214	1215	1216	1217	1218	1219	1220	1221	1222	1223	1224	1225	1226	1227	1228	1229	1230	1231	1232	1233	1234	1235	1236	1237	1238	1239	1240	1241	1242	1243	1244	1245	1246	1247	1248	1249	1250	1251	1252	1253	1254	1255	1256	1257	1258	1259	1260	1261	1262	1263	1264	1265	1266	1267	1268	1269	1270	1271	1272	1273	1274	1275	1276	1277	1278	1279	1280	1281	1282	1283	1284	1285	1286	1287	1288	1289	1290	1291	1292	1293	1294	1295	1296	1297	1298	1299	1300	1301	1302	1303	1304	1305	1306	1307	1308	1309	1310	1311	1312	1313	1314	1315	1316	1317	1318	1319	1320	1321	1322	1323	1324	1325	1326	1327	1328	1329	1330	1331	1332	1333	1334	1335	1336	1337	1338	1339	1340	1341	1342	1343	1344	1345	1346	1347	1348	1349	1350	1351	1352	1353	1354	1355	1356	1357	1358	1359	1360	1361	1362	1363	1364	1365	1366	1367	1368	1369	1370	1371	1372	1373	1374	1375	1376	1377	1378	1379	1380	1381	1382	1383	1384	1385	1386	1387	1388	1389	1390	1391	1392	1393	1394	1395	1396	1397	1398	1399	1400	1401	1402	1403	1404	1405	1406	1407	1408	1409	1410	1411	1412	1413	1414	1415	1416	1417	1418	1419	1420	1421	1422	1423	1424	1425	1426	1427	1428	1429	1430	1431	1432	1433	1434	1435	1436	1437	1438	1439	1440	1441	1442	1443	1444	1445	1446	1447	1448	1449	1450	1451	1452	1453	1454	1455	1456	1457	1458	1459	1460	1461	1462	1463	1464	1465	1466	1467	1468	1469	1470	1471	1
---	---	---	---	---	---	---	---	---	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---







NO.	DATE	REVISED	BY	CHK	DATE	BY
<p align="center"><b>HIGH TONGUE RIVER DAM SITE MAP</b></p>						
<p align="center"><b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</b></p>						
DESIGNED DRAWN <i>SM VALDEA</i> CHECKED <i>EL</i>		PROJ ENGR <i>R.H.</i> MGR SP PROJ <i>EL</i> MGR ENGR		APPROVED DATE		DESIGNED BY BY
6694		6694 - II - 003				

**BECHTEL CORPORATION**  
SAN FRANCISCO





### III. WATER SUPPLY STUDIES

#### GENERAL

In order to determine the firm yield of the Tongue River Project and the correlated reservoir storage capacity, a series of studies was made. These studies were based on an allocation of water under the Yellowstone River Compact. First, the historical inflow to the project area was determined. Second, the probable future depletion of flow above the state line by Wyoming under the provisions of the Yellowstone River Compact was subtracted from the historical inflow. Third, downstream releases for prior adjudicated rights on the Tongue River were deducted from the inflow. Fourth, the remaining water, called the storable inflow, was analyzed on a time sequence basis to determine the variation of the minimum storable inflow with time. Fifth, the minimum storable inflow was analyzed against time, evaporation and storage in order to evaluate the correlated firm water yield and required storage.

The water supply studies for the Tongue River Project are based on the "Water Allocation Study" report which developed the historical sequence of unused and unappropriated flows which could be allocated to Montana. That report was submitted to the Montana Water Resources Board on April 22, 1968 by Bechtel Corporation. The yield studies are based on the "Realistic Allocation" described in that report.

#### YELLOWSTONE RIVER COMPACT

A number of major rivers - the Clarks Fork of the Yellowstone River, Big Horn River, Tongue River, and Powder River - flow north from Wyoming into Montana to join the Yellowstone River. Beginning in the 1930's the states of Montana and Wyoming appointed Commissioners to study and determine the apportionment of water of these rivers between the states. During the 1930's and 1940's negotiations led to the signing of compacts which were not ratified by the legislatures. However, in 1950 an agreement including North Dakota was reached and a compact was signed at Billings, Montana, on December 8, 1950. The compact was subsequently ratified by the legislatures of the various states and by Congress.

The purpose of the Compact is "to remove all causes of present and future controversy between said states . . . with respect to the waters of the Yellowstone River and its tributaries . . . to provide for an equitable division and apportionment of such waters, and to encourage the beneficial development and use thereof."

The Compact provides that all appropriative rights to beneficial uses of the water of the Yellowstone River System existing in each state as of January 1, 1950, shall continue to be enjoyed in accordance with the laws governing the acquisition and use of water under the doctrine of appropriation. Further, the Compact provides that, of the unused and unappropriated waters of the interstate tributaries of the Yellowstone River as of January 1, 1950,



there is allocated to each state such quantity of that water as is necessary to provide supplemental water supplies for the appropriative rights existing as of January 1, 1950. Such supplemental rights are to be acquired and enjoyed in accordance with the laws governing the acquisition and use of water under the doctrine of appropriation. In the Tongue River, the remainder of the unused and unappropriated water is allocated 60 percent to Montana and 40 percent to Wyoming.

Nothing contained in the Compact is to be so construed or interpreted as to affect adversely any rights to the use of the waters of the Yellowstone River and its tributaries owned by or for Indians, Indian tribes, and their reservations.

The Compact provides a relatively simple formula for determination of the percentage allocations. The quantity of unused and unappropriated water subject to allocation is to be determined on an annual water year basis measured from October 1 of any year through September 30 of the succeeding year. The quantity to which the percentage factors shall be applied through a given date in any water year shall be, in acre-feet, equal to the algebraic sum of:

1. The total diversion above the point of measurement for irrigation, municipal and industrial uses in Wyoming and Montana developed after January 1, 1950;
2. The net change in storage in all reservoirs in Wyoming and Montana above the point of measurement completed subsequent to January 1, 1950;
3. The net change in storage in existing reservoirs in Wyoming and Montana above the point of measurement which is used for irrigation, municipal and industrial purposes, developed after January 1, 1950;
4. The quantity of water that passes the point of measurement in the stream.

The point of measurement in the Tongue River is below the last diversion from the river above its confluence with the Yellowstone River.

#### HISTORICAL INFLOW TO THE TONGUE RIVER PROJECT

Inflow to the Tongue River Project is measured by the gage -"Tongue River at State Line." This gaging station was installed in 1960 but the record has been extended back to 1945 by use of the records from the gages "Tongue River at Tongue River Dam and Tongue River Reservoir End-of-Month Contents." This extended record was then modified as described in the "Water Allocation Study" report. First, the record was reduced to



reflect the existence of the 1966 level of rights throughout the entire period. This was done on the "Part 2 - Wyoming" sheets in the "Water Allocation Study".

#### FUTURE DEPLETION IN WYOMING

The modified historical record was further reduced to account for the use of supplemental and surplus water in Wyoming on the basis of the "Realistic Allocation". The record of flow at the State Line gage reflecting the 1966 level of rights and realistic development of surplus and supplemental water in Wyoming is developed on the "Part 2 - Wyoming" sheets under the "Realistic Allocation". Wyoming's forty percent allocation of the unused and unappropriated water in the Tongue River, reduced for the post-1950 rights satisfied, was also deducted from the inflow. Wyoming's 40% share of the unused and unappropriated water was determined on the "Part 3 - Unused and Unappropriated Water" sheets under the "Realistic Allocation". The total for any year was assumed to be used for industrial purposes with annual consumption of 90% or 7.5% in each of the twelve months.

#### REQUIRED RELEASES

The decreed rights downstream of the Tongue River Project total 414.9 cfs. In addition to 30 cfs decreed rights, 60 cfs have been allotted to the Northern Cheyenne Indian Reservation as an allowance for water supply for their reserved lands as described in the "Water Allocation Study" report. This total of 475 cfs of prior rights are active during the irrigation season - May through September.

In the non-irrigation months, releases are required for stock water and for prevention of ice jams. This release has historically been the inflow to the reservoir up to 10,000 acre feet per month (equivalent to 167 cfs continuously). The minimum release required for fish and municipal uses is understood to be 35 cfs. An October through April average release of 75 cfs is judged necessary to provide a live stream and prevent ice jams.

The yield studies were made for May through September release of the natural inflow up to prior rights of 342 cfs. 342 cfs is  $.72 \times 475$  cfs and reflects rediversion and reuse of return flows as demonstrated by the Use Factor developed in the "Water Allocation Study". The winter release used in the yield studies was the natural inflow up to 75 cfs.

#### STORABLE INFLOW

The water available for development by the Tongue River Project is taken as the historical inflow to the project as modified by future depletion in Wyoming and reduced by the required downstream releases. This remainder, called the storable inflow, is determined by the calculation described in the following step-by-step description and illustrated on Table III-1:





## STORABLE INFLOW CALCULATION REALISTIC ALLOCATION:

Col 1      Year

Col 2      Month

Col 3      Flow - Tongue River at State Line - with 1966 Level of Rights,  
Surplus up to 220 cfs and Sheridan Canal -  
From Col 26 Part 2, Wyoming sheets in the Realistic Allocation.

Col 4      7.5% of The Annual Amount of Water Available for new  
Developments in Wyoming.

In the Realistic Allocation Study, the annual amount of water allocated to Wyoming under the Yellowstone River Compact was calculated. This was reduced by the amount of water used to satisfy Post 1950 rights in Wyoming. The remainder was considered to be used uniformly throughout the year and to be 90% consumed-10% appearing as return flow. 7.5% is the monthly equivalent of a 90% annual consumption.

Col 5      Net Inflow to Tongue River Reservoir - Col 3 minus Col 4.

Col 6      Releases to Satisfy Downstream Rights.  
Col 5 up to 342 cfs during May through September.  
Col 5 up to 75 cfs during October through April.

Col 7      Storable Water - Tongue River Reservoir.  
Col 5 minus Col 6.

## MINIMUM STORABLE INFLOW - FIRM YIELD - STORAGE

An approximate method for relating firm yield, storage and evaporation was presented in "Design Drouth Criteria" by Robert S. Gooch; Journal of the Hydraulics Division, ASCE, Vol. 92, No. HY2, March, 1966. The procedure consists of determining the annual minimum storable inflow based on the smallest one month storable inflow, the smallest two consecutive month storable inflow, the smallest three consecutive month smallest inflow, etc., plotting these annual storable inflow values against the number of months represented, and drawing the lower envelope curve of the points. A digital computer program is used to calculate the R vs. N points from the chronological storable inflow record. The resulting points and curve are shown on Drawing No. 6694-111-001.

Using points on the lower envelope curve; time, storage, yield, storable inflow and evaporation are related by the basic equation:

$$Y = \frac{C}{N} + R - L$$

Where Y = firm yield in Acre Feet per year.

C = required active reservoir capacity in Acre Feet.

N = drought period in years.

R = storable inflow corresponding to the drought period  
(determined from the graph described above) in Acre Feet per year.





L = losses in Acre Feet per year.

An allocation of water between Wyoming and Montana could not be made for the years prior to 1945 because there was no continuous record of flow in the Tongue River at Miles City. A continuous record of flow in the Tongue River at the Montana-Wyoming state line was developed back to 1929 by using the Tongue River at Tongue River Dam and Tongue River Reservoir, End-of-Month Contents gages for the period 1939-1960, and the Tongue River near Decker gage for the period 1928-1938. This extended record was then adjusted to show the effect of the 1966 level of rights during the entire period. R vs. N curves were made for the periods 1929-1966 and 1945-1966 using the adjusted record on the basis of the 1966 level of development. The R vs. N curves were compared, and correlation factors to bring the 1945-1966 curve to the 1929-1966 curve were developed. These correction factors were then applied to the 1945-1966 "Realistic Allocation" R vs. N curve to extent its applicability to the 1929-1966 period.

The correction factors and the corrected curve are shown on Drawing No. 6694-III-001.

### LOSSES

Although there will be seepage losses from the reservoir, it is judged that most seepage losses will reappear in the river downstream from the reservoir and therefore they will be small when compared with evaporation. For purposes of the yield studies, irrecoverable seepage losses are taken as 1000 Acre Feet per year for Stage I and 2000 Acre Feet per year for Stage II when more pervious strata may be below the higher storage level and head will be greater.

U.S. Weather Bureau records for the station at Terry, Montana, show pan evaporation of about 48 inches for the season May through October. Applying the normal .70 reduction factor for land vs. reservoir evaporation, this gives lake evaporation of 33.5 inches.

From the USWB map of normal annual Class A pan evaporation, the Tongue River Project area has about 40 inches of evaporation - 31 inches occurring in May through October.

Using an evaporation amount of 32.5 inches, and subtracting the normal seasonal precipitation of 12 inches, a loss of 20.5 inches is obtained. The average water surface area for the Tongue River Project is 3000 acres. Therefore the average annual evaporation is 5000 acre feet which was used in the firm yield studies.

Total annual losses used in the yield studies are 6000 acre feet for Stage I and 7000 acre feet for Stage II.

### SILTATION

The original gross reservoir capacity (from original topography) in 1939 was 72,510 acre feet with 1900 acre feet in dead storage. A U.S. Bureau of Reclamation (USBR) siltation survey in 1948 found (by soundings) that the capacity had been reduced to 69,440 acre feet of which 1400 acre feet was dead storage. In that nine year period, some 340 acre feet per year of silt was deposited in the reservoir of which 275 acre feet per year was deposited in active storage.



The 1948 U.S.B.R. storage vs. elevation curve was used to develop the present total storage curve shown on Drawing 6694-III-002.

A siltation and dead storage allowance of 21,000 acre feet has been adopted in addition to the required active storage to provide silt storage through the year 2008 with some 600 acre feet of dead and silt storage remaining at that time.

It must be recognized that this siltation analysis is based on minimal data. After the increased Tongue River Reservoir has been in operation for some 15 or 20 years a siltation survey should be made as a check on reduction of storage.

### ANALYSIS

A series of computations to determine the relationship between various storages and yields were made. The area and capacity curves are shown on Drawing No. 6694-III-002. The results of the yield and gross storage (including siltation and dead storage) calculations are shown on Drawing 6694-III-003.

### DETERMINATION OF FIRM YIELD - OPERATION STUDY

In order to check the accuracy of the approximate method described above, a reservoir operation study was made using a computer program from Bechtel's program library. The agreement between the approximate method and the operation study was within 6%, well within the limits of accuracy of the data.

### CONCLUSIONS

The analysis shows that a maximum of 112,000 acre feet per year of firm yield will be available for development based on the "realistic allocation" and full industrial use of Wyoming's share of the unused and unappropriated water. To develop this amount of firm yield, a gross reservoir storage of 450,000 acre feet is required which will provide for 12 years of carryover.

For the Stage I development of 100,000 acre feet per year of firm yield, a gross reservoir storage of 320,000 acre feet per year is required. The Stage I storage provides for ten years of carryover.

Part of the firm yield of the Tongue River Project is for downstream agricultural uses as provided by the existing Tongue River Irrigation Reservoir which will be inundated by the new reservoir.

### RESERVOIR FILLING STUDIES

A study has been made to determine probabilities of filling the reservoir in various periods of time. The firm yield of the Stage I project has been based on beginning a critical drought period of ten years with the reservoir at full storage level. Therefore the reservoir must be filled before its operation can be considered as providing firm yield.



The 21 years of record from 1946 through 1966 were analyzed. Because it is not known when the reservoir will be constructed, it must be recognized that different conditions of flow may exist in the future due to upstream development. Therefore, three cases of water use assumptions were studied:

- Case I:

1966 level of upstream development. Prior rights releases May through September;inflow up to 342 cfs. Winter releases: inflow up to 75 cfs. 30,000 acre feet assumed released to satisfy downstream agricultural contracts.
- Case II:

Same as Case I except that 37,000 acre feet of water is consumed by industrial development upstream in Wyoming.
- Case III:

Full "Realistic Allocation" development upstream in Wyoming. Prior rights releases May through September: inflow up to 342 cfs. Winter releases: inflow up to 75 cfs. 30,000 acre feet per year assumed released to satisfy downstream agricultural contracts.

The Stage I reservoir volume of 320,000 acre feet was filled, assuming that 30,000 acre feet were contained in the existing reservoir at start of filling.

The results of the filling probability studies are presented in the following Table:

	PERCENTAGE PROBABILITIES OF FILLING STAGE I TONGUE RIVER RESERVOIR					
	<u>1 Yr.</u>	<u>2 Yr.</u>	<u>3 Yr.</u>	<u>4 Yr.</u>	<u>5 Yr.</u>	<u>6 Yr.</u>
Case I	9	48	78	96	100	100
Case II	6	32	53	74	90	100
Case III	0	11	30	53	80	100

A four to six year filling period therefore should be provided on the basis of the inflow Case which pertains at the time the project is financed.





TONGUE RIVER PROJECT

342 and 75 cfs RELEASES

(1)	(2)	(3)	(4)	(5)	(6)	(7)
Year	Month	Flow Tongue River at State Line with 1966 level of rights surplus up to 220 cfs and Sheridan Canal	*7.5% of the annual amount of water available for new developments in Wyoming	Net inflow to Tongue River Reservoir (3) - (4)	**Releases to satisfy downstream rights; up to 342 cfs during the irrigation season and up to 75 cfs during the winter	Storable Water Tongue River Reservoir (5) - (6)
		cfs	cfs	cfs	cfs	cfs
1962	Oct.	295	131	164	75	89
	Nov.	233	131	102	75	27
	Dec.	155	131	24	24	0
1963	Jan.	183	131	52	52	0
	Feb.	336	131	205	75	130
	Mar.	219	131	88	75	13
	April	366	131	235	75	160
	May	1286	131	1155	342	813
	June	2552	131	2421	342	2079
	July	394	131	263	263	0
	Aug.	116	131	0	0	0
	Sept.	147	131	16	16	0

\*Water available is Wyoming's 40% share of U&U, less water used to satisfy Post 1950 rights

\*\* 342 cfs at Tongue River Dam serves 475 cfs of rights along the Tongue River in Montana (including Indian rights)



MINIMUM STORABLE INFLOW IN 1000 ACRE-FEET PER YEAR

200

190

180

170

160

150

140

130

120

110

100

90

80

70

60

50

40

30

20

10

0

CORRECTION FACTORS - PERCENT FOR 1929 - 1966			
CONSECUTIVE MONTHS	MIN INFLOW IN 1000 A F Period of Record 1929 - 1966	FACTORS PERCENT Period of Record 1945 - 1966	
12	3	27.5	11
24	38	48	79
36	56	64	87.5
48	68.5	77	89
60	78.2	88	88.6
72	87	96	90.5
84	95	104	91.5
96	102	110	93
108	109	116	94
120	116.5	123	94.5
132	124	128.5	96.5
144	131	134	98
156	138	140.5	98
168	144	145	99
180	149.8	150	100
192	155	155	100
204	160	160	100
216	165		100
228	170		100
240	175		100

SURPLUS WATER WYO.	SUPPLEMENTAL WATER WYO.	INDUSTRIAL WATER WYO.	IRRIGATION RELEASE May - Sept.	WINTER RELEASE Oct-April
Up to 220 cfs	REALISTIC Allocation Sheridan Canal - Dayton Reservoir Project	7 1/2 Percent monthly of Wyoming's annual share of unused and unappropriated water reduced by water to satisfy post 1950 rights	Inflow up to 342 cfs	Natural Inflow up to 75 cfs

1945-1966 Lower Envelope of  
Minimum Storable Inflow

Minimum Storable Inflow

1929-1966 Adjusted Envelope  
Minimum Storable Inflow

PERIOD OF TIME IN CONSECUTIVE MONTHS

BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED: H. ST  
DRAWN: H. ST  
CHECKED: H. ST

PROJ ENGR: R. ST  
HGR SP PROJ: R. ST  
HGR ENGR: R. ST



WATER SUPPLY STUDIES  
MINIMUM STORABLE INFLOW

TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA

APPROVED: 6694  
DATE: 6694 - III - 001








DESIGNED		PROJ. ENGR.		DATE	
DRAWN: SHIMADA		MGR. SP. PROJ.		DRAWING No.	
CHECKED: RAS		MGR. ENGR.		6694	
<p>WATER SUPPLY STUDIES RESERVOIR AREA AND CAPACITY</p> <p>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</p>				<p>6694 - III - 002</p>	

**BECHTEL CORPORATION**  
SAN FRANCISCO







Firm yield and storage requirements based on Minimum Storable Inflow - Realistic Allocation Study - Downstream Releases 342 cfs Irrigation and 75 cfs winter flow



<b>BECHTEL CORPORATION</b>			
SAN FRANCISCO			
DESIGNED	PROJ ENGR	DATE	
DRAWN	MGR SP PROJ		
CHECKED	MGR ENGR		

WATER SUPPLY STUDIES			
YIELD - STORAGE - STORAGE ELEVATION			
TONGUE RIVER PROJECT			
MONTANA WATER RESOURCES BOARD			
HELENA, MONTANA			
APPROVED	DATE	REV	
6694	6694 - III - 003		



#### IV. FLOOD HYDROLOGY

In order to provide data for design of the emergency spillway, a flood hydrologic study was made. This study included a review of the historical flood records and a development of the Probable Maximum Flood (PMF) and Standard Project Flood (SPF).

##### HISTORICAL FLOODS

U.S. Geological Survey gaging stations have been operated on the Tongue River in the vicinity of the project as follows:

<u>Location</u>	<u>Dr. Area sq.mi.</u>	<u>Period of record</u>
At State Line near Decker	1,477	1960-present
Near Decker	1,610	1928-38
Below Tongue River Dam	1,770	1939-present

The maximum flood recorded since 1960 at the State Line station was 6,080 cfs on June 16, 1963. The flood of June 2, 1929, with a peak discharge of 7,220 cfs, was the highest at the station near Decker from 1928 to 1938. At the station below the dam, the maximum flood since 1939 occurred on June 5, 1944, when a peak discharge of 6,180 cfs was observed.

Noteworthy floods prior to the period of record occurred in June 1908 and June 1916, but the discharges of these floods are not known.

##### FLOOD OF JUNE 1964

On June 7-8, 1964, a very large rainstorm occurred over northwester Montana (10). This storm was typical of other large rainstorms which have occurred along the eastern flanks of the northern Rocky Mountains. Because of its significance and because a similar storm could be expected anywhere along the mountain front, it has been used for development of the PMF.

##### PROBABLE MAXIMUM FLOOD

Criteria. The probable maximum flood inflow to the Tongue River Reservoir is based on the transposition and maximization of the June 7-8, 1964, storm over Northwest Montana.

##### PROBABLE MAXIMUM PRECIPITATION

To transpose the storm over the Tongue River basin above Tongue River Dam, the isohyetal map of the storm of June 7-8, 1964, was used. (8) This isohyetal map was oriented in such a way that the maximum average precipitation was obtained over the drainage area of 1740 square miles. Care was taken not to rotate the storm more than 5°. By planimetry



areas between isohyets an average precipitation of 7.35 inches over the drainage area was calculated. A coefficient of 1.35 was used to adjust the storm to maximum conditions. (7)(6) The transposed and maximized storm would have a total maximum probable precipitation in 36 hours of  $1.35 \times 7.35 = 9.92$  inches. Using the same depth-area-duration as observed for the storm of June 7-8, 1964, the 9.92 inches of probable maximum precipitation was distributed as follows:

<u>Time</u> (Hours)	<u>Accumulated Depth</u> (Inches)
1	0.71
3	1.78
6	3.24
9	4.68
12	6.31
15	7.10
18	7.99
24	8.96
30	9.55
36	9.92

UNIT HYDROGRAPH - 3 HOURS DURATION

Due to the great similarity in climatic and topographic conditions between the drainage area above existing Tongue River Dam and the Hole-in-the-Wall drainage area, the lag curve developed by the Bureau of Reclamation was used, as well as the dimensionless unit graph for the Tongue River near Dayton. (5)(6)(1) The final 3-hour unit graph was obtained following the procedure described by the Bureau of Reclamation. (4)

INFILTRATION

A retention rate of 0.25 inches per hour was used in the determination of the excess precipitation. Due to the similarity in soil, cover, and topography between the Hole-in-the-Wall basin and the drainage area above the existing Tongue River Dam, the same retention rate was used for both basins.

DESIGN INFLOW FLOOD HYDROGRAPH

Figure IV-1 shows the design flood at Tongue River Dam based on the design 36-hour rainfall, a uniform retention rate of 0.25 inches per hour and the three-hour unit hydrograph. This event is characterized by a peak discharge of 183,200 cfs and a total volume of 346,700 acre-feet. The increments of excess rainfall were re-arranged by trial to produce the maximum flood peak. The base flow of 3420 cfs, as used in the final computation of the inflow design flood, was obtained from analysis of recorded floods in the Tongue River basin.





SNOWMELT ANALYSIS

For analysis of snowmelt, the maximum floods in the Tongue River above the Tongue River Dam were selected. Three stations on the Tongue River were chosen as most representative of the basin. Due to the difference in areas above the stations, the relationship was developed between drainage area and snowmelt volume for a three-day period. By checking the daily precipitation records for the Sheridan station, the straightline corresponding to May, 1947, was selected as the best correlation factor in the snowmelt computation. (2) (3) (10) (9) Figure IV-2 shows the snowmelt studies.

ENVELOPE CURVE

Using the envelope curve for peak discharge in the Missouri River basin, developed by the Bureau of Reclamation, (5) the reading of the curve at 1740 square miles indicated a peak discharge of 70,000 cfs, which is 38.2 percent of the probable maximum peak flood.

STANDARD PROJECT FLOOD

A standard project flood (SPF) was developed and found to have a peak inflow of about 87,000 cfs.

The SPF when routed through the reservoir was found to have a peak outflow of 44,000 cfs.

TAILWATER RATING CURVE

Figure IV-3 shows the tailwater rating curve for the Tongue River immediately downstream from the Project site. The tailwater ratings were developed from field survey data which has been collected from a 2.5 mile downstream reach. A high and a low Manning's n value was used in both the main channel and the overbank.

These values represent the extremes of practical values which might occur in the river, and were assumed to be:

	High n	Low n
Main channel	.035	.028
Overbank	.060	.040




## REFERENCES

- 1) U.S. Bureau of Reclamation, "Memorandum on Inflow Design Flood Study -- Hole-in-the-Wall Dam Site -- Powder River Basin, Wyoming," March 9, 1965.
- 2) United States Weather Bureau: Climatological data, "Daily and Hourly Precipitation Data."
- 3) United States Geological Survey, Surface Water Supply Papers, Part 6-A, "Missouri River Basin Above Sioux City, Iowa."
- 4) U.S. Bureau of Reclamation, "Design of Small Dams," 1965. Chapter 2, Flood Studies.
- 5) U.S. Bureau of Reclamation, "Feasibility Inflow, Design Flood Study for Hole-in-the-Wall Dam Site," from James No. Horn, Regional Project Development Engineer, 2/2/65.
- 6) U.S. Bureau of Reclamation, "Memorandum on Revised Design Storm -- Hole-in-the-Wall Dam Site -- Powder River Basin -- Wyoming," November 2, 1964.
- 7) Data on the June 7-8, 1964 Storm in Northwest Montana in the Headwater Drainage of the Missouri River, furnished by Harold Grout, USBR, Denver.
- 8) "Isohyetal Pattern Storm of June 7-8, 1964 Northwestern Montana," Received 6/27/67, from USBR, Denver.
- 9) United States Geological Survey, Surface Water Records of Montana.
- 10) U.S. Department of Commerce, Weather Bureau, "Climatological Data," Wyoming.
- 11) "Floods of June 1964 in Northwestern Montana", U.S. Geological Survey, Water-Supply Paper 1840-B.



PRECIPITATION IN INCHES



TIME IN HOURS

-  Combined Losses
-  Excess Precipitation




FIGURE IV - 1








FIGURE IV - 2






FIGURE IV - 3



## V GEOLOGIC SUMMARY

### INVESTIGATIONS

The geological explorations for the Tongue River Project were carried out in two phases. The first phase, conducted during the summer and fall of 1967, explored the general geology of the project area and site geology at the existing Tongue River Dam and two new downstream sites. After determination of project storage requirements and adoption of a plan for development at the Four Mile Creek site, a second phase of specific site geological studies was made for the High Tongue River Dam in the summer of 1968. These second phase studies were made to develop additional specific design data for that dam.

### GENERAL GEOLOGY

The Tongue River is one of many rivers that flow north and north-eastward from the northwest trending Continental Divide in western Montana and northwestern Wyoming. It originates in Wyoming on the northeast flank of the Big Horn Mountains, a vertically uplifted fault block trending northwestward across the Montana-Wyoming border. After leaving the Big Horn Mountains, the river meanders across the Great Plains Province to its confluence with the Yellowstone River near Miles City, Montana.

The surface of the Great Plains Province in the vicinity of the Tongue River Project is composed of well stratified sedimentary rocks of continental origin deposited during erosion of the ancestral Rocky Mountains. These sedimentary rocks are part of the Fort Union Formation which is Eocene in age.

Post-Eocene mountain building resulted in uplift and formation of the Big Horn Mountains. The Tongue River came into being and began eroding its way through the sedimentary rocks until presently it has downcut several hundred feet below the original plain and formed the Tongue River valley.

The Big Horn Mountain uplift upwarped the western edge of the Fort Union Formation and other sedimentary units, but the deformation did not affect the beds in the vicinity of the Tongue River dam sites. These strata are essentially flat-lying, unfolded, and unfaulted.

### LOCAL GEOLOGY

From the Tongue River Dam to Four Mile Creek, the Tongue River has cut into the Fort Union Formation forming a valley from 100 to 350 feet deep and about 1300 feet wide. The strata of the Tongue River Member of the Fort Union Formation are well exposed in steep cliffs along the river and consist primarily of siltstone, sandstone, and an unusual sequence of baked sandstone and shale and some coal beds. Several coal beds in the siltstone unit are traceable for some distance, but thicken and thin along their outcrop.

The weathered exposures of sandstone are typically light yellow to buff and the siltstone is light gray. Cores of unweathered sandstone are buff to light gray and the siltstone is gray to dark gray.





The Tongue River Member is a continental deposit and possesses the sedimentary features common to sediments deposited under intermittent, torrential conditions. Features such as variation in thickness within a relatively short horizontal distance, pinching out of strata, cross bedding, and cut-and-fill structures are present at many places along the cliffs. Rock units at the three sites investigated generally showed consistency in thickness and elevation of particular beds but differences were observed.

#### COAL BEDS AND BAKED ROCK

The portion of the Tongue River valley studied lies in the northward extension of the Sheridan coal field. The coal is sub-bituminous with several beds being of commercial thickness and quality. These beds crop out along the cliffs of the valley and are easily recognized.

A unique bedrock feature in and around the Tongue River valley is the presence of prominent, resistant, cliff forming exposures of baked sandstone and shale. These rocks are brick red to salmon color as a result of baking from the burning of underlying coal beds. Sandstone beds have been altered in color and hardness but are still recognizable as sandstone. The siltstone beds have been hardened in some cases to porcellaneous shale and fused to slag. The baked rocks are locally referred to as "clinker" and "scoria", but the majority of the rock is recognizable as sandstone and shale.

The burned coal left voids that induced collapse of the overlying baked rocks producing collapse breccia. Cooling of the baked rocks produced contraction joints and horizontal partings along incipient bedding in siltstone which furthered breakdown of the rock. Because of the many fractures and joints the baked rocks are extremely permeable, but yet resistant to erosion because of their hardness.

The coal fires burned at the outcrops and where overburden was relatively thin, large surface areas were baked, but where overburden was thick, the baking extended less far back into the hill, but still often for several hundred feet. The vagaries of such baking are exhibited by rapid lateral change from baked to unbaked rocks.

The strata dip south beneath the floor of the valley. The local coal beds with engineering and geologic significance to this study are the Canyon bed, the underlying Wall bed, and several thin local beds between these two main beds. In exposure these beds have been burned and have been replaced by baked rock. However, where burning did not take place, as in the subsurface, the beds are still fresh coal. The Wall bed dips beneath the Tongue River just north of the Four Mile Creek site and is not exposed from there to the existing dam. The thick coal bed encountered in DH-1 at the High Tongue River dam site and DH's 3,5,6, 7 and 8 at the Oxbow site, is believed to be the Wall bed. The greatest thickness of this bed, now baked rock, in exposures north of Four Mile Creek is 32 feet, but where penetrated in drill holes at the Oxbow site it is 54 feet of coal and 60 feet of coal beneath High Tongue River Dam Site. To the north of Four Mile Creek the bed thins and eventually becomes several thin beds separated by siltstones.



Three to four local beds ranging in thickness from one to four feet are present in the vertical interval of 150 feet above the river surface and whether these local beds are continuous from the existing Tongue River dam to Four Mile Creek is not certain, but beds having approximately the same elevation and thickness are found at the three sites.

The Canyon bed is baked in exposures which rim the valley and is easily recognized by its brick red color. The bottom of the Canyon bed is generally about elevation 3450 to 3500.

#### NATURAL GAS SEEPS

Residents along the river in the vicinity of the dam sites report seeps of natural gas bubbling up through the river. The bubbling is especially noticeable during low stands of the river when the water is less turbulent and when the river is frozen over. The gas has been trapped in small containers and when ignited, burns with a blue flame.

Five locations were cited where natural gas has been reported in the river:

1. Near the U.S.G.S. stream gaging station below the dam.
2. Near Mr. Lee's house at his ranch.
3. Mr. Thompson's meadow.
4. Near the old water wheels at the Oxbow site.
5. At High Tongue River Dam site - Drill holes 104 and 105.

#### HIGH TONGUE RIVER DAM SITE

Physiography. The site is about 6000 to 7000 feet upstream of the confluence of Four Mile Creek and the Tongue River. The valley floor is from 700 to 1200 feet wide and is flanked on the left by two terrace levels reaching as high as 125 feet above the valley. On the right 40 to 45 degree slopes as high as 300 feet form the abutment. The sequence of bedrock units consists of interbedded sandstone and siltstone.

Geologic Exploration. The geologic exploration consisted of: (1) study of 1967 aerial photographs; (2) subsurface mapping at a scale of 1" = 100', shown on Drawing 6694-V-007; (3) drilling twelve exploratory NX core holes; and (4) the measurement of five stratigraphic sections, and the drilling of fourteen seven-inch auger holes.

All holes at High Tongue River Dam site, except at the right abutment (DH-1, DH-2 and DH-4), were provided with a 1-1/2 inch diameter coupling and plug, set in a concrete plug at the top of the hole. These couplings mark the hole locations for future use.

Stratigraphy. The uppermost rock unit is baked sandstone and shale which has broken down to form talus and debris aprons at the base of the unit. Underlying the baked rock unit is a siltstone unit containing some minor coal beds which in turn are underlain by a massive sandstone sequence. Beneath this, for the total depth drilled is another siltstone



unit which contains a 14-foot thick coal bed as found at the right abutment (DH-1).

The stratigraphy is illustrated on drawings 6694-V-008 and 008A.

#### Lithologic Units.

Alluvium. Exploratory drilling indicates that the silty sand and gravel in the channel section is as thick as 61 feet.

Terrace Deposits. Two nearly flat terrace surfaces are present at 75 and 125 feet above the valley floor on the left side. Exploratory drilling indicates that these sand and gravel deposits range from 10 to 20 feet thick.

Landslides. Several slope failures exist at the Four Mile Creek site, the most prominent of which is a landslide mass in the vicinity of DH-2. Geologic Section A-A' on Drawing 6694-V-008 shows a sequence of siltstone and coal in a stratigraphic position that should be occupied by massive sandstone. There is a seep near the upstream end of the slide area. Approximately 35 feet of talus and debris were encountered at the left abutment in DH-6. Other slope failures mapped in the vicinity indicate that several types of slope failures have occurred near the site.

Bedrock. Sedimentary rocks at the proposed site dip about 5 degrees south. The uppermost unit is baked sandstone and shale. Underlying this, from top to bottom, the strata are: siltstone containing minor coal beds, massive sandstone, and siltstone with sandstone interbeds and two thick beds of coal.

The dam abutments will be generally on the siltstone-coal and massive sandstone units. These units are generally weathered to depths ranging between 20 and 30 feet. Below the weathered zone, the rock contains relatively tight joints. The channel section will be in alluvium which is in direct contact with coal and/or siltstone.

Geologic Structure. The geologic structure is uncomplicated but there is a south and southwest dip consistent with the southward dip of such marker beds as the Wall coal. No faults or folds are known to exist at the site.

Prominent near-vertical joints control the shape of the prominent cliff. Joints and fractures in the cores are less frequent and tighter than in core from other sites.

Left Abutment. The base of the highly permeable baked rock is obscured by talus and slope wash but DH-6 encountered siltstone bedrock at elevation 3408 after going through talus and baked rock as determined by cuttings. Since no core was recovered from this interval, it is impossible to tell whether the baked rock is in place or is talus. Preconstruction drilling is required to clarify this question.

The gravel and sand terrace deposits are underlain, in descending order, by siltstone-coal and massive sandstone.

River Section. The 700 to 1200 foot wide valley floor is underlain by 27 to 61 feet of alluvium as determined in DH-3 and DH-101 respectively.





The underlying bedrock is interbedded siltstone and sandstone with layers of coal as thick as 57 feet. (DH-103). The depth to ground water ranges from 10 to 18 feet (July 1968).

Right Abutment. In the right abutment hill the base of the permeable baked rock is above the proposed second stage spillway crest elevation and reservoir seepage should not occur through this rock.

The massive sandstone in DH-4 appears to be good foundation rock.

Pressure Tests. Pressure tests show that water losses in the weathered rock were 20 to 30 gpm per 20 foot test increment using 1 pound of pressure per foot of hole. There was essentially no water loss in the unweathered rock.

Coal Beds. Several core holes, drilled in the river section area, encountered coal as shown on Geologic Sections A-A', B-B', and F-F'. The intervals of coal in the holes ranged from 31 to 57 feet although the greatest thickness of the coal may be 60 feet plus or minus 5 feet. Correlation of logs of all holes in this area is somewhat difficult as the bedding is lenticular and abrupt facies changes have occurred. Channel-cutting was probably taking place contemporaneously with, or just after, deposition of materials other than carbonaceous sediments. Examples of this channel cut-and-fill process have been observed on Tongue River upstream from the existing dam. Lensing and thinning of bedding can be seen in the right abutment at the Four Mile Creek site. It is not believed that faulting has caused the differences in elevation of similar lithologies as no surface evidence has been found to substantiate such a hypotheses.

A deep coal layer 57 feet thick was found in DH-103 at a depth of 133 feet below the ground surface in the river channel section.

It is improbable that a thick coal stratum, along Geologic Section A-A', is present from channel centerline westward to the left abutment. Coal is present under the right channel, and right abutment as well as upstream from the axis. In most holes encountering coal, alluvium is in direct contact with the coal and the original upper surface of the coal has been eroded away. Evidence for this is the large percentage of coal debris disseminated within the alluvium.

The lenticular nature of the bedrock strata is illustrated by Geologic Sections A-A', B-B' and Figure V-1. The same type of lenticularity downstream of High Tongue River dam axis is suggested by drill holes showing bedrock other than coal underlying the channel deposits.

The cores obtained in 1967 were re-examined in 1968. Some of the strata previously logged as siltstone and closely associated with the coal beds had slaked in the exposed core boxes. A sample was tested and found to be clay shale.



## SEISMICITY

The area of the Tongue River is not considered to be seismically active. During the period of record from 1852 to 1966, only one earthquake of intensity V or greater has had an epicenter within a 75-mile radius of the dam. This was an intensity V shock in 1925 with its epicenter about 38 miles south of Sheridan, Wyoming.

The Seismic Regionalization Map, Drawing 6694-V-010, in the supporting data shows the eastern half of Montana to be in a maximum intensity zone of VII which is one of the lower in the country.

The Seismic Probability Map, Drawing 6694-V-011, in the supporting data shows the site to be in Zone 1 where damage would be minor.

The closest, most recent major earthquake occurred at Hebgen Lake on August 17, 1959. The shock had a Modified Mercalli intensity of X at the epicenter which was located about 225 miles west of the Tongue River Dam.

An earthfill dam in the Tongue River area would sustain little damage from an earthquake of intensity VII whose epicenter was in the dam area. The probability of such a quake occurring is statistically low. It is recommended that a horizontal seismic factor of 10% be used for design.

## GEOLOGIC CONCLUSIONS

The geologic conditions present at High Tongue River Dam have been explored and were found to be suitable for construction of a dam of the proposed height.

The foundations are relatively strong. However, strata of baked rocks are highly pervious and coal layers are expected to be moderately pervious. Therefore seepage control must be provided for both these materials. It is anticipated that a combination of grouting and downstream drainage including relief wells, will provide effective seepage control.

The lithologic characteristics of the rock indicate generally low permeability. But since there are local more permeable strata a grout plan and procedure was designed to reduce this permeability to an acceptable minimum.

The cost estimate for grouting is based on the assumption that grout holes 70' - 140' deep with initial spacing of 10 feet and closer spacing of 5 feet and a grout acceptance of about 1 cu.ft. of cement to each lineal foot of grout hole will be adequate. This figure does not include a grout extension into either abutment.








FIGURE V-1

Exposure on Tongue River of the Tongue River Member (Fort Union Formation) showing lenticular sandstone beds (indicated by dots). Note cut-and-fill channel structure in sandstone bed and abrupt pinch-out on right side. Thin coal beds (black) mark undulating contact between sandstone and siltstone. This 120 foot cliff illustrates interbedded, lenticular conditions found in drill holes at High Tongue River Dam.





# EXPLANATION

- QUATERNARY**
- Talus + Slope Wash.
  - Silt, sand, gravel and boulders derived from weathering and breakdown of steep slopes
  - Qal: Alluvium silt, sand and gravel in river bottom and lowlands
  - Cal + Qal: Colluvium + Alluvium: locally derived slope wash merging with alluvium
  - Q1: River terrace deposits silt, sand and gravel; characterized by well rounded predominantly sedimentary gravel and distinctive igneous talus
  - Baked Ss + Sh: Locally referred to as "clinker" and "scoria"; red baked sandstone and shale, platy to closely broken and jointed, some vesicular "scoria"; has distinctive red brick color, extremely permeable.
  - Sist: Siltstone gray laminated to massive; commonly closely broken and jointed, yellow staining and occasional gypsum filling in joints, some clayey beds, ravels when weathered; contains coal beds and some carbonaceous siltstone beds
  - Coal: Black crumbly; includes earthy coal and other prominent carbonaceous beds, coal beds range from <1' to >4' in thickness
  - Ss: Sandstone, buff to gray very fine to medium-grained with some coarse-grained sequences; weakly to moderately well cemented strata; massive to thinly bedded with occasional cross bedded sequences relatively free of joints and fractures; contains little to no coal.

## SYMBOLS

- Line of Geologic Section
- Line of Measured Stratigraphic Section
- 1967 Drill Hole
- 1968 Drill Hole (IDQ Number Series)
- Geologic contact; dashed where inferred; queried where doubtful

Geology mapped July 1967

### REFERENCE DRAWINGS

- Stratigraphic sections shown on Dwg no 6694-X-009
- Geologic sections shown on Dwg no 6694-X-008



Topographic Map  
by  
R M TOWILL, CORP  
Date of photography June 26, 1967  
SCALE 200 0 200 400 Feet  
Contour Interval 5 Feet

## HIGH TONGUE RIVER DAM SITE GEOLOGIC MAP

TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA


BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED: [Signature]  
DRAWN: [Signature]  
CHECKED: [Signature]  
PROJ. ENGR. [Signature]  
MGR. SP. PROJ. [Signature]  
MGR. ENGR. [Signature]

APPROVED: [Signature] DATE: [Signature]  
JOB No. 6694 DRAWING No. 6694-X-007







MONTANA  
 I GEORGE  
 THON  
 1850 E  
 H. Thon

200 0 200 400 600 800 FT

NO.	DATE	REVISIONS	BY	CHKD	DATE	PAGE

HIGH TONGUE RIVER DAM SITE  
 LOCATION OF DRILL HOLES AND SECTIONS

TONGUE RIVER PROJECT  
 MONTANA WATER RESOURCES BOARD  
 HELENA, MONTANA

APPROVED	DATE	REV

<b>BECHTEL CORPORATION</b> SAN FRANCISCO		
DESIGNED	PROJ ENGR	
DRAWN	MGR SP PROJ	
CHECKED	MGR ENGR	

A A  
 Line of Geologic Section  
 ⊕ DH 1967 Drill hole  
 ● DH 1968 Drill hole

400' To OH-4  
 DH-102








6694 - V - 008A







REFERENCE DRAWING  
1 For locations of stratigraphic sections see  
Dwg. no. 6694-X-007.


HIGH TONGUE RIVER DAM MEASURED STRATIGRAPHIC SECTIONS									
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA									
APPROVED		DATE		BY		FOR		REV	
6694		6694-X-009							

BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	DR. [Signature]	PROJ. ENGR.	[Signature]
DRAWN	DR. [Signature]	ASST. PROJ. ENGR.	[Signature]
CHECKED	DR. [Signature]	ENGR.	[Signature]




# DRILL HOLE 1

Elev. 3446  
N 50481, E 99736




# DRILL HOLE 2

Elev 3388  
N 51340, E 99800



# DRILL HOLE 3

Elev 3282  
N 50770, E 99260



Note See sheet 3 for explanation



J. H. Thon

BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	PROJ. ENGR.	APPROVED	DATE
DRAWN	MGR. SR. PROJ.	6694	6694 - V - 012
CHECKED	MGR. ENGR.		

HIGH TONGUE RIVER DAM GRAPHIC DRILL LOGS SHEET 1 OF 5			
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA			
NO.	DATE	REVISIONS	BY




# DRILL HOLE 4

Elev 3428  
N 48935, E 98206




# DRILL HOLE 5

Elev 3343  
N 51240, E 98240




# DRILL HOLE 6

Elev 3432  
N 51563, E 97080



# DRILL HOLE 7

Elev 3278  
N 52175, E 98420



Note See sheet 3 for explanation



*G. Thompson*

BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED BY *W. R. H. H.* PROJ ENGR *RCH*  
DRAWN BY *BOCK* NICE SP PROJ NICE ENGR  
CHECKED *BOCK*

APPROVED DATE  
JOB NO. 6694 DRAWING NO. 6694 - V - 013 REV


HIGH TONGUE RIVER DAM  
GRAPHIC DRILL LOGS  
SHEET 2 OF 5  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA







# DRILL HOLE 101

Elev 3298  
N 50102, E 97751




# DRILL HOLE 102

Elev 3279  
N 49371, E 98080




# DRILL HOLE 103

Elev 3281  
N 50942, E 98892



# EXPLANATION



*G. Thon*


BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	<i>ack</i>	PROJ ENGR	<i>RCH</i>
DRAWN	<i>ack</i>	MGR SR PROJ	<i>ack</i>
CHECKED	<i>ack</i>	MGR ENGR	<i>ack</i>

NO	DATE	REVISED	BY	CS	DATE	NAME	DATE
<p>HIGH TONGUE RIVER DAM GRAPHIC DRILL LOGS SHEET 3 OF 5</p> <p>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</p>							
APPROVED		DATE		JOB NO.		DRAWING NO.	
6694		6694 - V - 014					




# DRILL HOLE 104

Elev 3268  
N 50617, E 99334




# DRILL HOLE 105

Elev 3282  
N 50395, E 98997




# DRILL HOLE 106

Elev 3292  
N 50492, E 98405




# DRILL HOLE 107

Elev 3288  
N 50444, E 98445




# DRILL HOLE 108

Elev 3285  
N 50763, E 98645




# DRILL HOLE 109

Elev 3280  
N 51022, E 98673



# DRILL HOLE 110

Elev 3281  
N 51211, E 98780



Note See sheet 3 for explanation



*J. George Thon*

BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED *AK* PROJ ENGR *RCN*  
DRAWN *AK* MGR SP PROJ  
CHECKED *AK* MGR ENGR


APPROVED  
JOB No. 6694  
DRAWING No. 6694 - V - 015  
DATE  
REV

HIGH TONGUE RIVER DAM  
GRAPHIC DRILL LOGS  
SHEET 4 OF 5  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA




# DRILL HOLE III

Elev 3287  
N 51225, E 98698




# DRILL HOLE II2

Elev 3279  
N 51485, E 98729




# DRILL HOLE II3

Elev 3277  
N 51492, E 98787




# DRILL HOLE II4

Elev 3275  
N 51610, E 98797




# DRILL HOLE II5

Elev 3275  
N 51600, E 98749




# DRILL HOLE II6

Elev 3277  
N 51451, E 98957




# DRILL HOLE II7

Elev 3277  
N 51412, E 99114




# DRILL HOLE II8

Elev 3282  
N 50425, E 98774



# DRILL HOLE II9

Elev 3273  
N 50286, E 99215



Note See sheet 5 for explanation



BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED: DGL  
DRAWN: J. G. Smith  
CHECKED: DGL

APPROVED: DATE: 6694 6694-X-016

HIGH TONGUE RIVER DAM  
GRAPHIC DRILL LOGS  
SHEET 5 OF 5  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA





## VI. CONSTRUCTION MATERIALS

### BORROW AREA EXPLORATIONS

The borrow area investigation was conducted between July 10, 1967 and September 16, 1967. The investigation consisted of excavating pits with a backhoe to depths up to 13 feet or until water conditions or bedrock made digging impractical. The average pit depth was approximately 11 feet and the sides of the pits were logged and sampled. Bags of soil representing the different classifications were taken from the sides of the pits and the pits backfilled. The borrow investigation was conducted for two locations; the existing Tongue River Dam and the Four Mile Damsite. Detailed descriptions of these explorations are described for each site in the following sections.

#### TONGUE RIVER DAM

Explorations for borrow materials were conducted in the valley along Leaf Rock Creek, on the Left Abutment and in Borrow Areas A, B, C and E. Photo-contour maps of these borrow areas as well as the logs and soil test data are presented in the Supporting Data.

The Leaf Rock Creek borrow area is approximately 8000 feet long by 600 feet wide and composed of an alluvial filled valley overlain by fine-grained material. A total of 8 backhoe pits were dug in this area, and the logs are shown on Drawing No. 6694-VI-009. The fine-grained materials are clays and silts mixed with fine-grained sands usually being of low plasticity and with layers of clean sands and gravels scattered throughout. Generally this finer material appears to be at least 12 to 13 feet deep in the lower portion of the valley. In the upper 2000 feet of the valley, the fine-grained material decreases in thickness to only about a foot.

The left abutment and Borrow Areas A and B contain gravelly materials. The logs of pits from these areas are shown on Drawing No. 6694-VI-010. At the left abutment there are 8 to 10 feet of gravel above the bedrock but the area is small and represents only a small quantity. Borrow Areas A and B are relatively small and the water table is near the surface. The area consists of sandy gravel of unknown depth covered with 3 to 7 feet of silts and silty sands. Because the gravel would have to be removed from below the water table and the apparent small quantity, these areas were not considered to be of great importance other than perhaps for filter or aggregate production.

Borrow Area C is a generally level field adjacent to the river. Three pits in this area indicate silty and clayey sandy gravels overlain in some parts by 4 to 5 feet of silty clay (logs are shown on Drawing No. 6694-VI-011.) The clayey material is of small quantity. Gravelly material would require processing to be used as filter, drain or aggregate material.



Borrow Area E is divided into a lower flat portion and a terraced portion. Four pits in the flat portion indicated 8 to 11 feet of clayey, silty, sandy soil averaging approximately 9 feet in depth. (See logs on Drawing No. 6694-VI-011). Pits in the terraces indicated sandy gravel with some fines.

#### HIGH TONGUE RIVER DAMSITE

Borrow Areas G, H, I, K, L, M, N, P, R and two far removed areas, D and Post Creek, were all investigated as sources of material for the High Tongue River damsite. Quantities of materials and their distance from the damsite are shown on Table VI-1. Borrow area maps and logs are presented in the Supporting Data.

Borrow Area R is a large field with a low level portion and a terraced portion. A total of 10 pits were dug and the logs are shown on Drawing No. 6694-VI-018. The level portion is composed of clay and silt and silty sand overlying clean sand and gravel. The fine-grained material is of medium to low plasticity and stratified with thin sand and gravel layers and ranges in depth from 4 feet to 12 feet and averages 10 feet deep. The terraces are composed of fairly clean sandy gravel and should average 8 feet deep. This sandy gravel would require some processing but is generally cleaner than in other areas.

Borrow Area P is in the dam foundation area and also has a low level portion and a terraced portion. Drawing No. 6694-VI-017 shows the logs from this area. In general, the level area is silty sand and silty gravel overlain by 2 to 5 feet of sandy silt. The terraced portion contains silty sandy gravel and extends to depths up to 12 feet or greater on the tops of the terraces and averages about eight feet. Processing would be required to produce filter, drain or aggregate materials.

Borrow Areas M and N are two generally level fields adjacent to the river. Two pits were dug in each field and their logs appear on Drawing No. 6694-VI-016. M is composed of approximately 8 feet of sandy slightly clayey silt overlying sand and gravel with the silt stratified with thin sand and gravel layers. N is composed of approximately 10 feet of silty gravelly sand generally stratified.

Borrow Area L is a large level field which lies between the toe of the slope and the river. Eight pits were excavated in this area and their logs are shown on Drawing No. 6694-VI-015. The area is composed primarily of clays, silts and silty sands. The clayey material nearer the toe of the slope is 11 to 12 feet in depth and overlying sands and sandy gravel. The soil near the river tends to be sandier and 5 to 10 feet deep above the sandy gravel. However, the fine-grained material should average at least 9 feet in depth.

Borrow Area K is a small level field. Drawing No. 6694-VI-013 shows the logs of 4 pits excavated in this area. The material consists of sand and sandy gravel overlain by clays, silts and silty sands. The fine-grained soils range from 4 feet to 12 feet and should average 10 feet deep.









Borrow Area H is made up of an alluvial fan portion and a terrace portion. Drawing No. 6694-VI-013 shows the logs of 6 pits in this area. The material is mostly sand and gravel with fines which would require that the gravel be processed for use as filter, drain or aggregate. The gravelly material ranges in depth from 6 feet to 13 feet and should average 8 feet deep.

Borrow Area G is made up of a low generally level portion and a terraced portion. Five pits were dug in the lower portion and four pits were dug in the terraced portion. Their logs are shown on Drawing No. 6694-VI-012. The terraced portion consists of sandy gravel overlain by 2 to 6 feet of silty clay and clayey silt. There should average 7 feet of sand and gravel. The lower portion is composed of sand and gravel overlain by 4 to 9 feet of silty clay and clayey silt. There should be approximately 4 feet of fine-grained material and 4 feet of sand and gravel from this area.

Borrow Area I is generally a level hay field. Eight pits were located in this area and logs are shown on Drawing No. 6694-VI-014. This area consists of clean sand and sandy gravel overlain by silts, clayey silts and silty sands. The fine-grained material varies in thickness from about 3 feet to about 8 feet averaging approximately 5 feet. Sand and gravel obtained from this area would have to be removed from below the water table and would require processing for use as filter, drain or aggregate. The quantity of gravelly material is not known.

Borrow Areas D and Post Creek are two areas farthest from the damsite. Two pits were put into each area and their logs are shown on Drawing No. 6694-VI-019. Post Creek is a long narrow very rocky valley. The logs indicated sandy gravel with some boulders and the depth of the material may average 8 feet deep. Because of the location of D the limits of the area were not defined. The logs of the two pits indicate 5 to 8 feet of sandy silt or fine-grained silty sand.

### CONCRETE AGGREGATES

The most feasible local source of concrete aggregates would be located on the upper terraces. While these areas were not specifically investigated for concrete aggregates the grain size distribution curves are available from the borrow area explorations. It is not known at this time as to whether these upper terrace deposits would meet acceptable concrete aggregate tests. The gravel deposits lying along the present streambed contain an appreciable amount of sedimentary and softer rocks and are therefore less likely to be acceptable.

The nearest known commercial sources of concrete aggregates are located at Sheridan, Wyoming where three firms are producing acceptable materials. The aggregate deposits are all located on the upper terraces west of town and are from a similar geologic period to those found along the Tongue River.

The concrete aggregate used in the present dam came from a pit located a few miles upstream of the dam. Nothing is known regarding the aggregate plant, the resulting product or the type of cement used.



## RIPRAP

No known sources of good, hard, sound rock are located along the Tongue River. A fairly firm cemented sandstone rib was visually examined and rejected for being too soft for long life. A small possibly useful sandstone layer is present near the High Tongue River damsite as described in the Geological Summary. Baked sandstone and shale, locally known as clinker, while frequently used for road surfacing would produce very little material larger than six inch size. Nearest possible source of an igneous rock that might be suitable for riprap is located in the Big Horn Mountains approximately 40 miles to the southwest. The lack of good riprap was recognized during the construction of the existing dam and thickness was increased from 30 inches to 15 feet measured normal to the slope with the material being the above-mentioned baked shale. The present condition of the upstream face appears to be satisfactory.

Exposures of baked shale occur at or slightly above the present reservoir while at the Four Mile Dam Site the baked shales are located along the tops of higher ridges generally above any proposed dam.

## TESTING

Representative samples of all materials encountered in the explorations were sent to Northern Testing Laboratories at Billings, Montana, for classification tests. Complete test data is presented in the Supporting Data, Part VI.

Samples of materials found to be representative of material types and areas were sent to Geo-Testing, Inc., San Rafael, California, for more complete testing, including shear, consolidation, compaction and permeability tests. Complete test data on the comprehensive testing and summary of all the testing performed is included in the Supporting Data, Part VI.

The soil properties adopted for design are presented in Part VII, Embankment - Stability Analysis.



## VII. EMBANKMENT

### GENERAL

The dam embankment is designed for economical raising from Stage I, to Stage II as shown on Dwg. No. 6694-VII-007 and 008. Studies of economical dam height and spillway combinations, considering the two-stage construction requirements, indicated that a spillway width of about 200 feet would be preferable. The Stage I spillway crest will be at El. 3438 with dam crest at 3464, providing some two feet of freeboard above the probable maximum flood water surface. The Stage II spillway crest will be at El. 3453 with a dam crest at 3476, again providing 2 feet of flood freeboard.

The spillway bridge beams had to have adequate clearance from the spillway upper nappe water surface profile. The first stage bridge had to be located nearly in the same position downstream and above the spillway crest as it is for the second stage. Therefore, the spillway crest walls are full height to support the bridge in the Stage II position. The Stage I dam embankment is also set at the Stage II crest El. 3476 adjacent to the spillway to provide access over the bridge.

### DAM ALIGNMENT

The placement of the dam was developed to take advantage of the most favorable foundation configuration and geologic conditions on the site.

A possible axis was investigated some 2000 feet upstream. The left abutment at that location is steeper and contains more baked rock and the spillway alignment would have been longer and required more excavation. However, the primary reason for rejecting an upstream axis, such as along the geologic section B-B shown on Dwg. No. 6694-V-007A, is the almost continuous thick coal bed encountered in borings along that location.

A shift of the dam alignment downstream would have moved the maximum section of the dam into a slide area mapped on the right abutment (Section D-D, Dwg. No. 6694-V-007A). Again, the spillway alignment would have been longer and substantially greater excavation would have been required.

Along the selected alignment, shown on Dwg. No. 6694-VII-001, the Zone 1 impervious core has good contact with the abutments. Right abutment contours converge downstream. On the left abutment the Zone 1 core contact is well keyed into an existing draw.

### DAM SECTION

The dam embankment section has been designed to:

1. provide adequate safety against low foundation shear strength,
2. provide seepage control within the embankment,





3. provide partial seepage control for pervious foundation layers,
4. provide for economical use of available earth construction materials.

The embankment has been designed with relatively flat slopes: Four horizontal to one vertical on the upstream slope and  $2\frac{1}{2}$  horizontal to one vertical with a series of wide berms on the downstream slope.

These embankment proportions were necessary to reduce shear stresses on lenses of weak clay shale in the foundation. A full description of the studies used to guide the proportioning of the embankment slopes and berms are presented in the section "Stability Analysis".

In order to provide seepage control within the embankment, two features were adopted. First, the impervious core, embankment Zone 1, is placed upstream and extended through streambed alluvium and terrace gravels to bedrock to act as a water barrier. The more pervious shell, Zone 4, supports the impervious core zone. The second seepage control feature is the drain chimney and blanket, processed gravel Zone 2 flanked by select gravel zone 4a. This chimney and drain blanket acts to collect all seepage within the embankment and conduct it safely downstream. The chimney drain also acts to reduce danger from cracking of the core, by providing a highly pervious, filter protected zone which can carry water away from cracks while permitting the core and filter to "heal" by washing in fines.

The embankment provides for foundation seepage control in two ways. First by placing the impervious core trench through the streambed alluvium and terrace gravels to bedrock to reduce seepage through those materials. In addition, by placing the impervious core trench upstream, a longer seepage path and reduced gradient is provided through the bedrock. The second foundation seepage control feature is that provided by the drain trenches under the downstream toe of the embankment. These drains trenches collect seepage through the streambed alluvium and terrace gravels, and relieve hydrostatic uplift at the most critical area, the downstream toe of the dam.

The zoning of the dam embankment includes several features which provide for economical usage of natural earth materials. Large amounts of required excavation are included in the High Tongue River Dam design, mainly in the outlet works, spillway, dam foundation and right abutment shaping. Therefore, a large random zone 4 shell has been provided to utilize nearly all the required excavation. A large random zone 4 has been provided in the center of the dam to provide an area for use of early excavation with only minimal foundation preparation. The zone 1 core must be obtained from upstream borrow areas. The use of the processed gravel drain zone 2 has been minimized. The filter zone 4a makes use of unprocessed sand and gravel from terraces or streambed. The zone 3, baked rock or "clinker", zone has been provided for drawdown and erosion protection. This baked rock is readily obtainable from the left abutment ridge above the dam.



## EMBANKMENT AND FOUNDATION SEEPAGE

The patterns of embankment and foundation seepage pressures developed for the various cases of stability analysis are shown on Dwg. Nos. 6694-VII-020 through 025. Equipressure lines are used to illustrate the seepage pressure patterns.

The upstream drawdown zone is considered highly pervious when compared to other materials. The core Zone 1 and central random Zone 4 are assumed to have equal low permeability, less than one foot per year. The chimney drain will be highly pervious. The foundation alluvium is considered pervious and the bedrock is considered to have much higher horizontal than vertical permeability due to horizontal siltstone and clay shale layers. The pressure at the downstream toe in the foundation bedrock is considered to be 10 feet higher than the relief well drain header to approximate well entrance hydraulic losses.



## STABILITY ANALYSIS

The stability analysis for the combined embankment and foundation was performed using a computerized circular arc method of slices. The method of analysis is illustrated on Dwg. No. 6694-VII-020. The results of the analysis on the final dam section are presented on Dwgs. No. 6694-VII-020 through -025.

Embankment soil parameters for the analysis as shown on the drawings were obtained from soil test data and are summarized below"

<u>Key</u>	<u>Zone</u>	<u>Type Mat'l</u>	<u>Unit Weight</u> <u>lb/cu.Ft.</u> <u>Moist Saturated</u>		<u>Friction</u> <u>Angle-</u> <u>degrees</u>
A	3	Baked Rock or clinker	77	115	33.5
B	1	Impervious Core	126	135	31.5
C	2,4,4a	Shell, drain & filter	131	131	31.5

Foundation parameters were generally determined from test data and typical data from other projects. However, the strength of the clay shale received some special attention. Because of the difficulty in sampling and obtaining meaningful test data on clay shales, only limited testing was performed. It was found that the clay shale had an Atterberg liquid limit of 51 percent, a plasticity index of 29 percent, and 52 percent smaller than 2 microns. Since shear strength determinations of the clay shale by testing would probably not be valid, indirect methods were used. Several block landslides in the area were analyzed. It was found that they could have failed by sliding on a base of clay shale with a developed friction angle of 20°. Similar values for clay shale shear strength were utilized in the design of Garrison Dam, North Dakota, also located in the Tongue River Member of the Fort Union Formation.

The foundation for the dam consists of layers of coal, sandstones and siltstones. These layers generally lense out in short distances as described in the section "Geology". Therefore, the clay shale is also found in discontinuous layers. The stability analysis had to reflect the field conditions. A wedge type analysis, failing along a horizontal continuous clay shale bed, is therefore, unrealistic. Consequently a circular arc analysis was selected to pass through lenses of clay shale in the foundation. For purposes of analysis, this was done by setting 5 foot thick layers of clay shale in the siltstones and sandstone 30 feet apart. Because the circular arc analysis made by the computer can stay within a five foot thick layer only for a short distance, the effect of lensing is realistically achieved.

A summary of the foundation strength parameters is as follows:





<u>Key</u>	<u>Type Mat'l.</u>	<u>Saturated Unit Weight</u>	<u>Friction Angle Degrees</u>
D	Streambed Alluvium Terrace Gravel	130	30.0
E	Siltstone and sandstone	137	30.0
F	Clay shale	137	20.0

The results of the stability analysis are summarized in the following table.

<u>Section</u>	<u>Condition</u>	<u>Safety Factor</u>	
		<u>Design Criteria</u>	<u>Computed</u>
Upstream - Maximum	Gravity-Seepage	1.50	1.81
Upstream - Maximum	Gravity-Seepage-Seismic	1.10	1.16
Upstream - Maximum	Rapid Drawdown	1.25	1.40
Upstream - Abutment	Gravity-Seepage	1.50	1.81
Upstream - Abutment	Gravity-Seepage-Seismic	1.10	1.12
Downstream-Maximum	Gravity-Seepage	1.50	1.91
Downstream-Maximum	Gravity-Seepage-Seismic	1.10	1.16
Downstream-Abutment	Gravity-Seepage	1.50	1.66
Downstream-Abutment	Gravity-Seepage-Seismic	1.10	1.12

#### FOUNDATION SEEPAGE CONTROL

Foundation seepage control is partly provided by the embankment design as previously discussed. At the center of the impervious core zone contact with the bedrock, a grout curtain will be installed as detailed on Dwg. No. 6694-VII-005. Relief wells and horizontal pipe drains will be installed along the toe of the dam as shown on Dwgs. No. 6694-VII-004 and 006.

#### RIGHT ABUTMENT SLIDE AREA

The landslide area at the downstream right abutment toe of the dam will be buttressed by the dam embankment. Drains will be installed to relieve seepage pressures behind the slide material. In order to increase the stability of this slide area the right abutment ridge above the slide will be cut back to unload the top of the slope.

#### INSTRUMENTATION

Instrumentation will be required to determine the performance of the high Tongue River Dam and foundations. Embankment piezometers will be installed to monitor internal seepage pressures. Surface settlement markers and two cross arm internal settlement devices will be installed to monitor the surface settlements and internal distribution of embankment settlements.



The emphasis on instrumentation however, will be on monitoring foundation seepage in the coal and other pervious members. Open tube type wellpoints will be installed along the toe of the dam and in the abutments to determine the foundation seepage pressures and provide a basis for design of any necessary remedial treatment.

#### CAMBER


Camber will be provided to allow for anticipated crest settlement of one to two feet and provide for a slightly arched crest so that it will not appear to sag in the middle. Four feet of camber will be provided by oversteepening at the top of the dam, and tapering to no camber at the abutments.

#### ROADS

An access road will be provided by improving the existing road from the Decker-Birney road and building a new road to the left abutment of the dam as shown on Dwg. No. 6694-VII-001.









<b>BECHTEL CORPORATION</b> SAN FRANCISCO	
DESIGNED <i>EC</i>	PROJ ENGR <i>EC</i>
DRAWN <i>W. J. Smith</i>	MGR SP PROJ <i>W. J. Smith</i>
CHECKED <i>W. J. Smith</i>	MGR ENGR <i>W. J. Smith</i>

NO		DATE		REVISIONS		BY	CHK	REV	DATE
<p align="center"><b>HIGH TONGUE RIVER DAM STAGE I DAM PLAN</b></p> <p align="center"><b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</b></p>									
APPROVED		DATE							
FOR No.		6694		DRAWING No.		6694 - VII - 001		REV	







#### NOTES:

1. The lower layer of Zone 4a, shall have a thickness of 5 feet where the stripped foundation elevation is 3270 or higher. The thickness shall be increased where the stripped foundation is lower than El. 3270 to provide a top of layer elevation of 3275.

#### ZONE

#### MATERIAL

- 1 Impervious - from Borrow Areas R, M, L, G & I
- 2 Processed Sand and Gravel
- 3 "Clinker" or "Baked Rock"
- 4 Random - Required Excavation or from Borrow Areas R, M, L, G and Past Creek
- 4a Select Gravely fill from Terrace Borrow Area

**BECHTEL CORPORATION**  
SAN FRANCISCO

DESIGNED: *B. M.* PROJ. ENGR: *B. M.*  
DRAWN: *B. M.* HIGH SP. PROJ.: *B. M.*  
CHECKED: *B. M.* MGR. ENGR: *B. M.*







APPROVED: \_\_\_\_\_ DATE: \_\_\_\_\_  
JOB No. 6694  
DRAWING No. 6694 - VII - 002

**HIGH TONGUE RIVER DAM**  
**STAGE I DAM**  
**MAXIMUM SECTION**  
**TONGUE RIVER PROJECT**  
**MONTANA WATER RESOURCES BOARD**  
HELENA, MONTANA





ELEVATION



## NOTES:

1. The Toe Drain pipe shall be 12" Ø perforated clay tile or transite pipe.



J. H. Jones

20 0 20 40 60 80 100 FT

BECHTEL CORPORATION  
SAN FRANCISCO

DESIGNED: F. H. J. PROJ. ENGR. R. M. J.  
 DRAWN: H. H. MGA. SP. PROJ. E. J. J.  
 CHECKED: E. J. J. MGA. ENGR.

APPROVED

JOB No.

6694

DRAWING No.

6694 - VII - 003

DATE

REV

HIGH TONGUE RIVER DAM  
 DAM  
 ABUTMENT SECTION AND DETAILS  
 TONGUE RIVER PROJECT  
 MONTANA WATER RESOURCES BOARD  
 HELENA, MONTANA

















TYPICAL GROUT HOLE DETAILS

NOTES:

1. Elevations shown are views looking downstream
2. All alluvium, slope failure material, talus, slope wash and unconsolidated debris in core trench and along grout curtain will be removed
3. It is anticipated that grout holes will generally be spaced at 5 feet centers in a single curtain. Between section A-C, a double curtain may be required as determined by the Engineer



GROUT CURTAIN - PLAN  
SCALE 1" = 200'



BECHTEL CORPORATION



SAN FRANCISCO

DESIGNED *Bechtel* PROJ ENGR *Bechtel*  
DRAWN *S.H.S.* MGR BY PROJ *Bechtel*  
CHECKED *Bechtel* MGR ENGR *Bechtel*



APPROVED \_\_\_\_\_ DATE \_\_\_\_\_  
JOB NO. 6694 DRAWING NO. 6694 - VII - 005 REV \_\_\_\_\_

HIGH TONGUE RIVER DAM  
DAM  
GROUTING DETAILS  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA





SECTION A-A  
10 20 30 FT



RELIEF WELL - DOWNSTREAM  
TOE OF DAM (See A-1/2 2)  
NTS

# NOTES

1. Slope Relief Well drain header 0.5 % to discharge at Elevation 3268 at outlet works.
2. Relief Well at Spillway similar to Relief Well at Downstream Toe of Dam except as shown and noted on Eng 6694-III-010
3. Locations also shown on Eng 6694-III-004




*J. A. Engle*

BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	8/67	PROJ ENGR	8/67
DRAWN	11/67	MGR SP PROJ	8/67
CHECKED	8/67	MGR ENGR	8/67

NO	DATE	REVISIONS	BY	CHK	DES	APP	DATE
HIGH TONGUE RIVER DAM DAM DRAINAGE DETAILS TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA							
APPROVED		DATE		REV			
JOB No.		DRAWING No.		REV			
6694		6694 - VII - 006					







200 0 200 400 600 800 1000 FT



<b>BECHTEL CORPORATION</b> SAN FRANCISCO	
DESIGNED <i>[Signature]</i>	PROJ ENGR <i>[Signature]</i>
DRAWN <i>[Signature]</i>	MGR SP PROJ <i>[Signature]</i>
CHECKED <i>[Signature]</i>	MGR ENGR <i>[Signature]</i>

NO.	DATE	REVISIONS	BY	CHKD	DATE
<p align="center"><b>HIGH TONGUE RIVER DAM STAGE II DAM PLAN</b></p> <p align="center"><b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</b></p>					
APPROVED		DATE		BY	
6694		6694-VII-007			










$$\begin{array}{r} 44 \overline{) 72} \\ \underline{56} \phantom{00} \\ 16 \phantom{00} \end{array}$$

759 140 52

$$\frac{259}{265} \bigcirc \frac{131}{134}$$
$$\begin{array}{r} 22 \overline{) 440} \\ \underline{44} \phantom{0} \\ 0 \phantom{0} \end{array}$$
$$\frac{2.3}{2.8} \approx \frac{122}{127}$$
$$\begin{array}{r} 240 \text{ } ^{\circ} 39' \\ \underline{258} \text{ } 147' \end{array}$$
$$\frac{3.125}{24} \bigcirc \frac{65}{170}$$
$$\begin{array}{r} 4 \phantom{00} \cdot 78 \\ \underline{5.3} \phantom{00} 2.9 \end{array}$$

Si - 2 - 2 - 2 - 2 - 2 - 2  
1 - 1 - 1 - 1 - 1 - 1

METHOD OF ANALYSIS  
Circular Arc Method of Slices by Computer



Force in forces acting  
on body is 0

VECTOR KEY

- 3) -> "3D" weight of slice  $\cdot h \cdot r$
- > "Net" water force acting on base of slice = (UL - UR)
- > "Water" forces acting on base of slice =  $\rho$
- > "Component of slice normal" to base of slice
- 10) -> "Effective component of  $\sigma_c$  normal" to base of slice
- > "Component of  $\sigma_c$  to  $\rho$  normal" to base of slice
- 10) -> "Normal force" equal to  $\sigma_{10} \cdot ac$
- 11) -> "Effective normal component of  $\sigma_c$  including seismic force"
- 12) -> "Shear" component of  $\sigma_c$  including seismic force

### CALCULATION OF SAFETY FACTOR

$$FS = \frac{\sum \sigma_i \cdot \sin \phi}{\sum \sigma_i} \quad \text{Win EQUILIBRIUM}$$


2 - Reaction at the sliding base of slide

ASSUMPTIONS

1 - Inter-soil water stresses are neglected

2 - Inertia of soil (i.e.  $\rho \cdot a$ ) in horizontal direction is neglected

3 - Sliding force is due to total weight applied horizontally in the direction of motion (for positive base drag)



MAXIMUM DAM SECTION

• Equi pressure Lines

**BECHTEL CORPORATION**  
SAN FRANCISCO

DESIGNED	PROJ ENGR
DRAWN	MGR SP PROJ
CHECKED	MGR ENGR

APPROVED	DATE	REV
JOB No.	DRAWING No.	
6694	6694-VII-020	

HIGH TONGUE RIVER DAM  
 DAM STABILITY SUMMARY  
 UPSTREAM MAXIMUM SECTION - SHEET 1

TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA



3000 227 164 820 86 2610 3670

3070 2430 79 45 62 239 390

300 252 97 5 47 90 291

3580 2580 2580 2580 2580 2580 2580


354 256 256 256 256 256 256

# SO - DATA OBTAINED FROM LABORATORY TESTS

MATERIAL	UNIT WEIGHT, PCF		φ °
	Moist	Adjusted	
A	77	5	33.5
B	26	33	3.5
C	21	91	1.5
D	-	30	12.5
E	-	37	20.0
F	-	37	20.0

## SUMMARY OF RESULTS

A - 2 ELEVATION	ARCS 4V TO ELEV.	MINIMUM SAFETY FACTOR -	
		GEOTECHNICAL DATA	SEASONAL
3310	3170	25	40



Note: Foundation layers of clay are these are discontinuous and continuity is simulated as shown herein to facilitate stability analysis by computer.

MAXIMUM DAM SECTION

50 100 150 200 250 300 350 400 450 500 550 600 650 700 750 800 850 900 950 1000

BECHTEL CORPORATION

SAN FRANCISCO

DESIGNED BY M. J. [Signature]  
DRAWN BY M. J. [Signature]  
CHECKED BY M. J. [Signature]

PROJ. ENGR. R. L. [Signature]  
MGR. SP. PROJ. [Signature]  
MGR. ENGR. [Signature]

APPROVED

FOR FILE

6694

DRAWING NO.

6694 - VII - 021

DATE

REV

HIGH TONGUE RIVER DAM  
DAM STABILITY SUMMARY  
UPSTREAM MAXIMUM SECTION - SHEET 2  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA





8.2 197  
712 192

335 149  
332 152

213 122  
244 132

240 31  
280 49

388 79  
438 187

904 256  
302 263

148 208  
385 99

359 151  
394 158

223 22  
234 27

25 127  
251 138

318 65  
376 75

737 241  
989 248

137 220  
392 208

385 154  
431 162

241 24  
248 126

194 117  
222 126

271 50  
319 60

593 224  
753 231

408 57  
472 167

255 126  
276 133

90 112  
201 16

227 33  
265 44

467 203  
572 21

446 62  
515 172

267 26  
303 136

24 116  
22 116

90 10  
219 26

354 77  
426 57


54 169  
589 179

277 127  
334 141

250 121  
258 126

194 12  
203 116

261 148  
713 160



Note: Foundation layers of clay shale thickness discontinuous in situ continuity simulated as shown here only to facilitate stability analysis by computer

ABUTMENT DAM SECTION

0 50 100 150 FT

# SOIL DATA OBTAINED FROM LABORATORY TESTS

MATERIAL	UNIT WEIGHT - PCF		φ °
	Moist	Saturated	
A	77	115	33.5
B	126	135	31.5
C	131	31	30.0
E	-	137	20.0
F	-	137	20.0

## SUMMARY OF RESULTS

N° S ELEVATION	ARCS TAN TO ELEV	MINIMUM SAFETY FACTOR			
		GRAVITY		SEISMIC	
		Required	Computed	Required	Computed
3453	3323	1.50	2.14	110	115
	3293	1.50	2.29	110	122
3438	3323	1.50	2.03	110	113
	3293	1.50	2.16	110	119
3420	3323	1.50	1.90	110	112
	3293	1.50	2.01	110	116
3380	3323	1.50	1.81	110	118
	3293	1.50	1.85	110	116

## LEGEND

Gravity Case  
Arc Tangent E El 3400

Seismic Case  
Arc Tangent to E 3200

Gravity Case  
Arc Tangent E 3170

Seismic Case  
Arc Tangent to E 3170

## NOTES

1. See Drawing No 6694 - VII - 020 for a description of the method of analysis and assumptions

NO.	DATE	REVISIONS	BY	CHK	DESIGNED	DRAWN	CHECKED	INSP	APP	DATE
<p>HIGH TONGUE RIVER DAM DAM STABILITY SUMMARY UPSTREAM ABUTMENT SECTION</p> <p>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</p>										
<p>6694 VII - 022</p>										

<p>BECHTEL CORPORATION SAN FRANCISCO</p>			
DESIGNED	PROJ ENGR	CHKD	
DRAWN	MGR ST PROJ	CHKD	
CHECKED	MGR ENGR	CHKD	



# SOIL DATA OBTAINED FROM LABORATORY TESTS

MATERIAL	UNIT WEIGHT - PCF		G <sub>s</sub>
	Moist	Saturated	
A	77	115	33.5
B	86	135	31.5
C	131	131	31.5
D	-	130	30.0
E	-	137	30.0
F	-	137	29.0

## SUMMARY OF RESULTS


H.S. ELEVATION	ARCS TAN TO ELEV	MIN. SAFETY FACTOR	
		GRAVITY	Apparent Compacted
3453	3200	1.50	1.3
	3170	1.50	2.01
	3110	1.50	2.00
	3080	1.50	1.98

## LEGEND: Gravity Case

- Arcs tangent to El. 3200 → 2.47
- Arcs tangent to El. 3170 → 2.25
- Arcs tangent to El. 3110 → 2.00
- Arcs tangent to El. 3080 → 2.01

## NOTES

1 See Drawing No 6694 - VII - 020 for a description of the method of analysis and assumptions



## MAXIMUM DAM SECTION

0 100 200 300 FT

## BECHTEL CORPORATION

SAN FRANCISCO

DESIGNED BY J. J. ... PROJ. ENGR. R. L. ...  
DRAWN BY H. W. ... MGR. SP. PROJ. K. V. ...  
CHECKED BY T. E. ... MGR. ENGR. ...

APPROVED

DATE

JOB NO. 6694 DRAWING NO. HIGH TONGUE RIVER DAM STABILITY SUMMARY DOWNSTREAM MAXIMUM SECTION - SHEET 1 TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA

6694 - VII - 023



# SOIL DATA OBTAINED FROM LABORATORY TESTS

MATERIAL	UNIT WEIGHT - PCF		$\phi^\circ$
	Wet	Saturated	
A	77	135	33.5
B	126	135	31.5
C	131	131	31.5
D	—	130	30.0
E	—	137	30.0
F	—	137	29.0

## SUMMARY OF RESULTS

W.S. ELEVATION	ARCS TAN TO ELEV	MIN SAFETY FACTOR	
		Required	Computed
3453	3200	1.10	1.20
	3170	1.10	1.22
	3110	1.10	1.19
	3080	1.10	1.16

## LEGEND: Seismic Case

- 155 — Arcs tangent in El 3200
- 140 — Arcs tangent to El 3170
- 119 — Arcs tangent to El 3110
- 117 — Arcs tangent to El 3080

## NOTES:

1. See Drawing No 6694 - VII-020 for a description of the method of analysis and assumptions.



J. H. Thon


DATE		REVISIONS		BY	CHK	APP	DATE
<b>HIGH TONGUE RIVER DAM DAM STABILITY SUMMARY DOWNSTREAM MAXIMUM SECTION - SHEET 2</b>							
<b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</b>							
DESIGNED		PROJ ENGR		FOR FILE		BY	
DRAWN		WGR BY PROJ		DATE		BY	
CHECKED		WGR ENGR		DATE		BY	
6694		6694		VII-024			

## BECHTEL CORPORATION SAN FRANCISCO

DESIGNED: J. H. Thon  
DRAWN: J. H. Thon  
CHECKED: J. H. Thon  
PROJ ENGR: J. H. Thon  
WGR BY PROJ: J. H. Thon  
WGR ENGR: J. H. Thon

## MAXIMUM DAM SECTION

100 0 100 200 300 FT



Note: Foundation layers of clay shale. These are discontinuous in situ. Continuity is simulated as shown here only to facilitate stability analysis by computer.





429 90	330 176	273 164	241 152	315 76	312 169
472 86	302 59	239 146	231 142	261 147	396 173
475 82	302 50	239 133	231 134	261 149	396 176
475 79	312 49	230 133	235 130	270 146	375 170

# SOIL DATA OBTAINED FROM LABORATORY TESTS

MATERIAL	UNIT WEIGHT - PCF		$\phi^{\circ}$
	Moist	Saturated	
A	77	115	33.5
B	26	135	31.5
C	131	131	31.5
E	-	137	30.0
F	-	137	20.0

329 192	314 173	267 164	250 55	300 166	292 61
- 182	- 157	- 140	- 40	- 162	- 167
456 181	291 148	228 130	225 34	263 152	390 173
470 179	296 146	236 129	226 128	272 146	404 74

347 172	295 69	266 165	282 165	272 159	275 57
- 174	- 153	- 141	- 41	- 161	- 60
430 177	280 146	218 128	225 134	304 157	366 167
438 178	283 142	222 124	225 129	293 151	409 173

## SUMMARY OF RESULTS

W S ELEVATION	ARCS TAN TO ELEV	MINIMUM SAFETY FACTOR				REMARKS
		GRAVITY		SEISMIC		
		Required	Computed	Required	Computed	
3453	3323	150	208 166	110	128 112	Deep Seated Arc Toe Failure
	3293	150	-	110	130 124	Deep Seated Arc Toe Failure
	3263	150	216	110	128	-
	3233	150	211	110	122	-

302 160	271 163	280 170	320 177	24 147	268 147
- 162	- 148	- 146	- 150	- 152	- 153
387 165	267 143	216 129	238 138	311 157	343 161
432 174	271 140	211 122	230 132	318 156	364 168

256 146	245 155	382 204	334 179	206 132	335 56
- 148	- 143	- 160	- 158	- 140	- 149
326 155	281 138	236 139	270 147	283 148	326 -
381 165	260 137	215 125	251 140	322 152	363 -


## LEGEND

Gravity Case      Seismic Case

Arcs tangent to El 3323 → 280 170 → Arcs tangent to El 3323  
 146 → Arcs tangent to El 3293

Arcs tangent to El 3263 → 216 129 → Arcs tangent to El 3263  
 Arcs tangent to El 3233 → 211 122 → Arcs tangent to El 3233

208 128	248 156	897 294	331 179	166 112
- 130	- 149	- 210	- 160	- 24
267 139	238 135	343 171	306 156	246 136
315 150	251 134	282 150	303 152	288 146



## NOTES

1 See Drawing No 6694 - VII - 020 for a description of the method of analysis and assumptions

## ABUTMENT DAM SECTION

50 0 50 100 150 FT

NO	DATE	REVISION	BY	CHK	DESIGNED	DRAWN	CHECKED	DATE
<p align="center"><b>HIGH TONGUE RIVER DAM DAM STABILITY SUMMARY DOWNSTREAM ABUTMENT SECTION</b></p> <p align="center"><b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA</b></p>								
<p align="center"><b>BECHTEL CORPORATION SAN FRANCISCO</b></p>								
<p>DESIGNED: <i>M. J. F.</i> PROJ. ENGR: <i>R. N.</i>          DRAWN: <i>H. W.</i> MGR. SP. PROJ.: <i>K. V.</i>          CHECKED: <i>H. T.</i> MGR. ENGR: <i>J. J.</i></p>								
6694		6694 - VII - 025		<p>APPROVED: _____ DATE: _____</p>				



## VIII. SPILLWAY

### GENERAL

The spillway is located on the left abutment of the dam. A plan and profile of the spillway are shown on Drawings No. 6694-VIII-001 and -002. An ungated 200-foot long ogee crest is provided for both first and second stage construction. The decision to construct the dam in two stages had a significant influence on the spillway design. The Stage 1 construction will provide a maximum storage water surface of Elevation 3438. A cost analysis of dam height versus spillway configuration provided an economical combination of a 200-foot long spillway crest, maximum water surface for PMF discharge of 3462 and dam crest 3464. Design spillway outflow for Stage 1 is 94,000 cfs.

For second stage construction 450,000 acre feet of gross storage is required. This establishes the reservoir storage level at Elevation 3453, and the corresponding second stage dam crest at Elevation 3476 with flood pool at Elevation 3474. The flood routing study showed that maximum second stage spillway discharge will be 80,000 cfs.

### HYDRAULIC DESIGN

Design of the spillway crest thus required a first stage ogee which would discharge 94,000 cfs at crest Elevation 3438; and was capable of being raised to crest Elevation 3453 with a discharge capability of 80,000 cfs. The ogee design was based on Corps of Engineers' Hydraulic Design Criteria<sup>(1)</sup> using design heads of 21.0 feet for Stage 1 and 15.75 feet for Stage 2. The resulting maximum coefficients of discharge were 4.00 for Stage 1 and 4.13 for Stage 2.

Water surface profile for the spillway chute was computed using Manning's "n" equals 0.015.

Configuration of the stilling basin was determined by use of Bureau of Reclamation Criteria for a Type II basin.<sup>(2)</sup> The basin elevation was set to ensure that the jump  $D_2$  elevation would be below the tailwater elevation at all discharges.

### STRUCTURAL DESIGN

Structural design of the spillway was based on Corps of Engineers' Criteria<sup>(3)</sup> using the following loading conditions:

Maximum allowable bearing pressures

Approach walls not on rock = 2 Tons/sq.ft. plus overburden pressure.

All walls on rock = 6 Tons/sq.ft.



#### Lateral earth pressures

Approach walls and high walls at crest: (Counterforted)  
Saturated density 135 lb./cu.ft. - earth pressure coefficient 0.60.

Chute walls (Cantilever walls downstream of crest):  
Saturated density 130 lb./cu.ft. - earth pressure coefficient 0.35.

High walls at stilling basin (Counterforted):  
Saturated density 130 lb./cu.ft. - earth pressure coefficient 0.5.

#### Concrete

Minimum compressive strength at 28 days - 3000 lb./sq.in.  
Maximum allowable stress in flexure - 1350 lb./sq.in.

Reinforcement - Maximum allowable tensile stress - 24,000 lb./sq.in.

As mentioned above, the ogee and upper chute walls will be constructed in two stages; however, all other spillway features are built to their ultimate configuration during first stage construction as shown on Dwg.No.6694-VIII-002.

The ogee is founded on rock at approximate Elevation 3405, some 17 feet below the base of the approach channel. A shear key and seepage cutoff is provided at the upstream face of the ogee.

For second stage construction, the ogee crest will be raised to Elevation 3453. At the time of second stage construction the first stage crest will be stepped, and dowels will be provided to assure complete bond between the first and second stage concrete. The raised crest details are shown on Dwg. No. 6694-VIII-002 and 012.

A 200-foot long clear span plate girder bridge designed for H-20 loading provides a 12-foot roadway across the spillway crest at the second stage dam crest elevation as shown on Dwg. No.6694-VIII-11.

Counterforted approach walls with stepped footings are provided upstream of the spillway crest. These walls vary in height from 66 feet to 22 feet. For layout of the approach and abutment walls, see Drawings 6694-VIII-004 and -005.

A 200-foot wide, 1117-foot long rectangular chute conveys spillway discharges from the crest to the stilling basin. The upstream 880 feet of the chute is on a 7 percent grade approximately parallel to the natural ground surface; the remainder is on a 50 percent grade, terminating at the stilling basin floor. The chute is provided with L shaped cantilever walls 14 feet high in the upper reach and 12 feet high in the lower reach. These heights allow approximately six feet of freeboard at maximum discharge. The chute floor is a pattern of 30 foot by 30 foot, 18 inch thick slabs. In addition, the slabs are secured





to the foundation with twelve-foot long anchor bars spaced as shown. The chute is shown on Drawings 6694-VIII-006 and -007.

The 200-foot wide by 150-foot long rectangular stilling basin has 55 feet high counterforted side walls. The stilling basin floor is composed of 30-foot by 30-foot, 4-foot thick slabs provided with keys and waterstops at all joints. Fifty percent of the reinforcement is run through the joints. The slabs are anchored to the foundation by No. 11 bars in a 5-foot by 10-foot pattern. The bars are embedded 15 feet minimum into the foundation rock. Chute blocks, armored baffle blocks and an end sill are provided. Stilling basin layout and details are shown on Drawings 6694-VIII-008 and -009.

The entire spillway is protected from hydrostatic uplift by a system of underdrains. Beginning at the crest structure, a 6-inch diameter cross drain is located behind the shear key. This drain is tied to two 12-inch diameter longitudinal drains spaced 50 feet each side of the spillway centerline. The longitudinal drains extend the full length of the chute and at their lower end are turned laterally to discharge through the stilling basin walls. Along the chute six-inch diameter cross drains are provided at 60-foot spacing. As protection against freezing, and to assure collection of seepage water, the drains are located in 6-foot deep trenches which are backfilled with pervious material.

In addition to the underdrains, 8-inch diameter longitudinal drains are provided behind the chute and stilling basin walls. These are located approximately at foundation level and are daylighted through the stilling basin walls. Relief wells are provided around the stilling basin to protect against deep seated uplift. Drainage details are shown on Dwg. No. 6694-VIII-010.


#### REFERENCES

- (1) U. S. Corps of Engineers' Hydraulic Design Criteria - Waterways Experiment Station, Vicksburg, Mississippi.
- (2) Bureau of Reclamation "Design of Small Dams", 1960, Section 199, Hydraulic Jump Basin.
- (3) U. S. Corps of Engineers, EM-1110-2-2400, Structural Design of Spillways and Outlet Works, November 1964.













PROFILE



100 0 100 200 300 Ft

REFERENCE DRAWING

6694-VIII-001 Spillway Plan

BECHTEL CORPORATION  
SAN FRANCISCO


DESIGNED: [Signature] PROJ ENGR: [Signature]  
DRAWN: [Signature] MGR SP PROJ: [Signature]  
CHECKED: [Signature] MGR ENGR: [Signature]

APPROVED: [Signature] DATE: [Signature]  
JOB No. 6694 DRAWING No. 6694-VIII-002 REV


HIGH TONGUE RIVER DAM  
SPILLWAY  
PROFILE AND SECTIONS  
TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA









Crest Coordinates			
U/S Quadrant	V	D/S Quadrant	
-2.10	0.227	0.50	0.014
-3.78	0.810	1.00	0.038
-4.62	1.310	2.00	0.135
-5.04	1.65	4.00	0.489
-5.25	1.87	7.00	1.376
-5.46	2.13	12.00	3.73
-5.56	2.44	16.00	6.35
-5.67	2.65	25.00	14.51



- NOTES**
1. Protective cover for reinforcement shall be 3" for concrete placed against the ground.
  2. Reinforcement steel splices shall lap 24 bar diameters but not less than 12 inches.



**SPILLWAY CREST  
GEOMETRY**  
Scale 1"=10'-0"

**SPILLWAY CREST  
TYPICAL REINFORCEMENT & CONCRETE CLASS**  
Scale 1"=10'-0"



**DETAIL (1)**  
Scale 1"=1'-0"

**SPILLWAY CREST  
CONTRACTION JOINT**  
Scale 1"=10'-0"






**SECTION A**  
Scale 1"=10'-0"



NO.	DATE	REVISED	BY	CHK	DATE
<p align="center"><b>HIGH TONGUE RIVER DAM SPILLWAY CREST STRUCTURE DETAILS</b></p> <p align="center"><b>TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD</b></p> <p align="center">HELENA, MONTANA</p>					
APPROVED		DATE			
JOB No.		DRAWING No.		BY	
6694		6694-VIII-003			


<b>BECHTEL CORPORATION</b> SAN FRANCISCO	
DESIGNED: <i>[Signature]</i>	PROJ. ENGR. <i>[Signature]</i>
CHECKED: <i>[Signature]</i>	MGR. ST. PROJ. <i>[Signature]</i>
MGR. ENGR. <i>[Signature]</i>	



[illegible]


**BECHTEL CORPORATION**  
SAN FRANCISCO






GENERAL ARRANGEMENT


50 0 50 100 150 200 250 FT



PLAN-RIGHT ABUTMENT




SECTION @ LEFT ABUTMENT



SECTION @ BRIDGE

20 0 20 40 60 80 100 FT



SECTION @ D/S END



*J. H. Turner*

BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	J. A. Zier	PROJ ENGR	R. N. Turner
DRAWN	J. R. E.	MGR SP PROJ	R. N. Turner
CHECKED	T. R. E.	MGR ENGR	


NO.	DATE	APPROVED	BY	CHK	PROJ. ENG.	DATE	REV.
HIGH TONGUE RIVER DAM SPILLWAY CREST WALLS-GENERAL ARRANGEMENT							
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA							
APPROVED				DATE			
6694				6694-VIII-005			












**DETAIL 1**


Typ. anchor between Sta. 10+33 & 21+50 N.T.S.



**SECTION A-A**

Scale: 3/4"=1'-0"


Note: For details not shown see Sect. B-B



**SECTION B-B**

Scale: 3/4"=1'-0"


Note: Reinforcement not shown



**TYP ANCHOR PATTERN**

Between Sta 10+33 & 21+50

N.T.S.



**BECHTEL CORPORATION**  
SAN FRANCISCO

DESIGNED: J.E. PROJ. ENGR. R.E.N.  
DRAWN: MGR. SP. PROJ. R.V.T.  
CHECKED: MGR. ENGR.

APPROVED

DATE






HIGH TONGUE RIVER DAM  
SPILLWAY  
CHUTE SLAB - DETAILS

TONGUE RIVER PROJECT  
MONTANA WATER RESOURCES BOARD  
HELENA, MONTANA

6694

6694 VIII-007





NOTES:  
1 Reinforcement not shown.

20 0 20 40 60 FT




HIGH TONGUE RIVER DAM SPILLWAY STILLING BASIN - GENERAL ARRANGEMENT									
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA									
NO.	DATE	REVISIONS	BY	CD	DES.	CHK.	APP.		
APPROVED _____ DATE _____									
DRAWING NO. _____									
6694 6694-VIII-008									


BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	PROJ. ENGR.	CHKD.	
DRAWN	MGR. IN PROJ.	CHKD.	
CHECKED	MGR. ENGR.	CHKD.	









TYPICAL ANCHOR LAYOUT - SLABS 1-12




DETAIL OF TYPICAL LONGITUDINAL CONTRACTION JOINT




DETAIL OF TYPICAL TRANSVERSE CONTRACTION JOINT



DETAIL OF TYPICAL ANCHOR



DETAIL OF CHUTE BLOCK



DETAIL OF BAFFLE BLOCK


# NOTES




BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED	PROJ. ENGR.	DATE	
DRAWN	MGR. SP. PROJ.	DATE	
CHECKED	MGR. ENGR.	DATE	

NO.	DATE	REVISIONS	BY	CHKD.	APP'D.	REV.
HIGH TONGUE RIVER DAM SPILLWAY STILLING BASIN - DETAILS						
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA						
APPROVED		DATE		KEY		
6694		6694 - VIII - 009				







**DRAINAGE LAYOUT - PLAN**  
Scale 1"=100'-0"




**SECTION C-C**  
Scale 1"=2'-0"





**SECTION A-A**  
Typical for 7% chute  
Scale 1"=10'-0"



**SECTION D-D**  
Scale 1"=50'-0"




**SECTION B-B**  
Typical for 50% slope  
Scale 1"=10'-0"



J. H. Ann

BECHTEL CORPORATION SAN FRANCISCO				HIGH TONGUE RIVER DAM SPILLWAY DRAINAGE LAYOUT AND DETAIL			
DESIGNED	DRAWN	CHECKED	PROJ. ENGR.	DATE	DESIGNED	DATE	REV.
ELI	ELI	ELI	ELI	6694	6694	VIII - 010	





Hand-drawn plan view of a spillway structure. The diagram shows a rectangular spillway with a width of 200'-0" and a length of 204'-0" between supports. The total length including fixed and roller bearing supports is 103'-0". The spillway crest is divided into two stages: Stage II at elevation 3453.0 and Stage I at elevation 3438.0. The structure is supported by fixed supports on the left and roller bearing supports on the right. A detail view of the spillway crest is shown on the left. The drawing is dated 10-1-00.

Axis of crest Sta 9+83.0

Stage II Crest Sta 10+00

Bridge Sta 10+06

For Details of Abut. see Orig. VIII-005

Stage II Crest

Stage I Crest

11 3453.0

SECTION B-B

NOTES


1. Do not loading for H-20-44
2. Concrete shall be
3. All permanently chamfered  $\frac{1}{4}$  inch
4. Splices in reinforcement minimum of 24

REFERENCE


SECTION B-B

- 1 Des on loading for the bridge is AA54D  
H-20-44
- 2 Concrete shall be class A-14
- 3 All permanently exposed corners shall be chamfered  $\frac{3}{4}$ " unless otherwise shown
- 4 Splices in reinforcement shall be lapped a minimum of 24 bar diameters

DETAIL - BRIDGE DECK



DETAIL 1




DETAIL 2

NO	DATE	ED/SD/SD	BY	CT	PREP (DATE)	QRA (REV)	REV
<p>HIGH TONGUE RIVER DAM          SPILLWAY          BRIDGE - GENERAL ARRANGEMENT</p> <p>TONGUE RIVER PROJECT          MONTANA WATER RESOURCES BOARD          HELENA, MONTANA</p>							
APPROVED:						DATE	
JOB NO.		DRAWING NO.				REV	
6694		6694 - VIII - 011					








SECTION A-A      SECTION B-B



NOTES



54  
Girder

54  
Bridge

54  
Girder




X	Y	X	Y
5.10'	1.17"	56.10	9.57'
10.20'	2.28"	61.20'	10.08'
15.30'	3.33"	66.30	10.53'
20.40'	4.37"	71.40	10.92'
25.50'	5.25"	76.50	11.25'
30.60'	6.12"	81.60'	11.52'
35.70'	6.93"	86.70'	11.73'
40.80'	7.68"	91.80'	11.88'
45.90'	8.37"	96.90'	11.97'
51.00'	9.00"	102.00'	12.00'

### CAMBER DIAGRAM


<b>BECHTEL CORPORATION</b> SAN FRANCISCO		HELENA, MONTANA	
DESIGNED DRAWING CHECKED	PROJ ENGR MGR SP PROJ MGR ENGR	APPROVED JOB No.	DRAWING No. DATE
2246 6	RENT RUT	6694	6694 - VIII - 012





TYPICAL SECTION OF  
RAISED SPILLWAY CREST

20 0 20 40 60 FT



DISCHARGE  
CFS = 1000

SPILLWAY RATING CURVE



*T. W. 1850 E.*

<b>BECHTEL CORPORATION</b> SAN FRANCISCO		APPROVED _____ DATE _____ FOR MR. _____ DESIGNED <i>EL</i> PROJ. ENGR. <i>RET</i> DRAWN <i>M. J. H.</i> MGR. OF PROJ. <i>AVT</i> CHECKED <i>AVT</i> MGR. ENGR.		DRAWING NO. <b>6694 - VIII - 013</b>	EPT
---	--	--	--	---	-----

NO. DATE REVISIONS BY CTS PREP. DATE	
HIGH TONGUE RIVER DAM SPILLWAY RATING CURVE AND STAGE II CREST TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA	



## IX. OUTLET WORKS

### GENERAL

The outlet works are located in a trench through the low terrace on the left side of the river channel. General arrangement is shown on Drawing IX-001. The full length of the outlet works required for Stage II construction will be constructed to Stage I because of the great difficulty in moving the outlet structure downstream. The required capacity of the outlet works is based on two considerations: delivery criteria and capability to lower the storage pool.

The delivery criteria, based on minimum pool elevation 3310 are:

Industrial use	100 cfs
Prior adjudicated rights and allowance for reserved Indian lands	342
Existing Agricultural Contracts	<u>133</u>
Total	575 cfs

The delivery criteria would require a capacity to deliver 34,500 acre feet in any 30 day period.

It is judged that the outlet works should have sufficient capacity to release about one third of the second stage storage in 30 days. This amounts to reducing storage by about 150,000 acre feet in 30 days, which requires a discharge of 2500 cfs in excess of inflow. Except during the months of May and June, inflow is less than 500 cfs. Therefore the required design discharge has been established at 3000 cfs.

The outlet works are designed to meet the 3000 cfs discharge when the reservoir water surface is at elevation 3438. The outlet works capacity at minimum pool elevation 3310 is 1200 cfs. The elevation of the outlet valve centerline was set at 3280 to prevent submergence of the valve during spillway discharge. The plan and profile of the outlet works are shown on Dwg. 6694-IX-001.

### HYDRAULIC DESIGN

Outlet works hydraulics were computed on the basis of the following head losses:

Trashrack	$0.38 \frac{V^2}{2g}$
Entrance (bellmouth)	$0.05 \frac{V^2}{2g}$
Contractions	$0.10 \frac{(V_2 - V_1)^2}{2g}$
Expansion(12 Degrees)	$0.10 \frac{(V_1^2 - V_2^2)}{2g}$
Butterfly Valve	$0.40 \frac{V^2}{2g}$
Fixed Cone Valve	$0.41 \frac{V^2}{2g}$
Friction-Steel Lined Conduit-Mannings	"n" = 0.012
Exit	$1.0 \frac{V^2}{2g}$





The hydraulic design also included a study of the gates and valves provided for flow regulation and control.

At the upstream end of the conduit, a guard gate has been provided for emergency closure of the outlet works. This gate will be lowered from a barge by a diver, into slots in the intake structure.

A 108 inch diameter, hydraulically operated butterfly valve is located in the conduit. This valve is designed for 190 feet of head and for emergency closure in the event of failure of the downstream regulating valve. Closure time of the butterfly valve under emergency conditions will be controlled at 6 minutes to reduce the undesirable effects of rapid closure. Admission of air into the conduit after emergency closure will be provided by 7 - 10 inch diameter air inlet valves. One valve will be located immediately downstream of the butterfly valve and thereafter at 25 ft spacing.

At the downstream end of the conduit a 90 inch diameter, electrically operated, fixed cone dispersion valve is provided for regulation of outlet works discharges. Design of the outlet works is such that hydraulic control is at the downstream regulating valve under all conditions of flow.

#### STRUCTURAL DESIGN

The 10 foot diameter outlet works conduit is steel lined throughout. A 15 foot wide by 15 foot deep trench is excavated in bedrock and the space between the conduit and the trench filled with structural concrete, thus saving forming costs. The steel conduit is provided with external welded stud anchors to develop shell stiffening action with the concrete surround. The steel conduit is designed to resist the full reservoir head plus full internal vacuum as an external load.

The intake structure incorporates trashracks, a bellmouth transition and slots for the guard gate. The intake structure is shown on Dwg. 6694-IX-002.

The 108 inch diameter butterfly is housed in a chamber located in the impervious zone, foundation contact. The valve and chamber are shown on Dwg. No. 6694-IX-003.


Provision is made for withdrawal of industrial water by a 4-foot diameter tee located immediately upstream of the regulating valve. Initially the tee is capped with a blind flange.

A control building is located on top of the regulating valve structure. From this building, a six and one half foot high by eight foot wide manway provides access to the butterfly valve chamber. Piezometer gauges housed in an insulated and heated box are located near the downstream end of the manway. The outlet structure is shown on Drawing No. 6694-IX-004.

The conduit downstream of the butterfly valve may be dewatered and manholes have been provided for inspection of the conduit interior.




Circulation of air between the outside and the valve chamber has been provided through the air demand of the fixed cone dispersion valve.






PLAN

100 0 100 200 300 Feet



Typical - Sta. 10+00 to Sta. 15+03.




Typical - Sta. 16+17 to Sta. 25+97

10 0 10 20 30 Feet


BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED: <i>W. H. H.</i>	PROJ. ENGR: <i>R. H. H.</i>	DATE: <i>1/15/61</i>	
DRAWN: <i>R. H. H.</i>	HQA. SP. PROJ: <i>W. H. H.</i>	JOB NO. <i>6694</i>	
CHECKED: <i>W. H. H.</i>	HQA. ENGR: <i>W. H. H.</i>	DRAWING NO. <i>6694 - IX - 001</i>	

HIGH TONGUE RIVER DAM OUTLET WORKS PLAN PROFILE AND SECTIONS			
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA			
APPROVED: <i>W. H. H.</i>	DATE: <i>1/15/61</i>	BY: <i>W. H. H.</i>	






ROOF PLAN



SECTION A-A



SECTION B-B



# NOTES

A bulkhead gate fabricated from structural steel will be provided for emergency closure of the conduit. The gate will be stored at the left abutment of the dam.



BECHTEL CORPORATION SAN FRANCISCO			
DESIGNED DRAWN CHECKED	BY BY BY	PROJ ENGR WGR SP PROJ WGR ENGR	DATE





HIGH TONGUE RIVER DAM OUTLET WORKS INTAKE STRUCTURE - CONCRETE OUTLINE			
TONGUE RIVER PROJECT MONTANA WATER RESOURCES BOARD HELENA, MONTANA			
APPROVED	DATE	BY	
FOR NO.	DRAWING NO.	REV.	
6694	6694 - IX - 002		











**BECHTEL CORPORATION**  
SAN FRANCISCO

DESIGNED <i>EB</i>	PROJ ENGR <i>RCF</i>
DRAWN <i>S.B.M.</i>	MGR SP PROJ <i>LUT</i>
CHECKED <i>EB</i>	MGR ENGR <i>[Signature]</i>



## X. COST ESTIMATE

An order-of-magnitude estimate of the project cost for Stage I development has been prepared. This estimate is based on quantities for the major items of work calculated from the drawings presented in this report. The estimate considers three construction seasons will be required. The Specific Construction Cost corresponds to a construction contractor's bid, presented at a 4th Quarter, 1968, price level. Those items of project cost which can be estimated at this time are added to the Specific Construction Cost; contingencies, engineering, management of construction and part of the anticipated cost escalation. The 15% allowed for cost escalation covers the period from an undefined project release date through one year of pre-construction engineering and three years of construction. Excluded from the estimated Total Project Cost are those items which are to be determined by the Montana Water Resources Board after financing arrangements and the project schedule become known. These excluded items are the cost of land and rights of way, engineering costs already incurred, escalation from the present to the date of project release, financing costs and other client costs. In considering financing costs, it should be noted that interest on borrowed capital during reservoir filling is a significant item, since the time which must be allowed for reservoir filling is four to six years.





TONGUE RIVER PROJECT  
HIGH TONGUE RIVER DAM  
FOUR MILE SITE--CREST ELEVATION 3464

ORDER-OF-MAGNITUDE COST ESTIMATE

LAND AND LAND RIGHTS	(See Note)
RESERVOIR	\$ 35,000
EARTHFILL DAM	12,824,000
SPILLWAY	6,968,000
OUTLET WORKS	2,256,000
SITE IMPROVEMENTS	50,000
SUBTOTAL, SPECIFIC CONSTRUCTION COST, 4th Quarter, 1968, Price Level	<u>\$22,133,000</u>
ALLOWANCE FOR CONTINGENCIES	3,755,000
ENGINEERING	
To Date	Not Included
Pre Construction	422,000
During Construction	315,000
MANAGEMENT OF CONSTRUCTION	1,400,000
	<u>28,025,000</u>
SUBTOTAL	
	28,025,000
ALLOWANCE FOR COST ESCALATION	
4th Quarter, 1968, to Project Release	(See Note)
Project Release to Completion @ 15%	4,204,000
INTEREST ON BORROWED CAPITAL	
During Construction	(See Note)
During Reservoir Filling	(See Note)
CLIENT COSTS	(See Note)
	<u></u>
TOTAL PROJECT COST (less exclusions as noted)	\$32,229,000

Note: Cost to be provided by Montana Water Resources Board.







